A MECHANICAL COURSE FOR HIGH SCHOOLS

BY

ROBERT A. PERKINS

ARMOUR INSTITUTE OF TECHNOLOGY

1917

607
P 42

AT 465
Perkins, R. A.
A mechanical course for high
schools

Digitized by the Internet Archive
in 2009 with funding from
CARLI: Consortium of Academic and Research Libraries in Illinois

http://www.archive.org/details/mechanicalcourse00perk

A MECHANICAL COURSE FOR HIGH SCHOOLS

A THESIS

PRESENTED BY

ROBERT AUGUSTUS PERKINS

TO THE

PRESIDENT AND FACULTY

OF

ARMOUR INSTITUTE OF TECHNOLOGY

FOR THE DEGREE OF

MASTER OF SCIENCE

IN

INDUSTRIAL ARTS

MAY 31, 1917

ILLINOIS INSTITUTE OF TECHNOLOGY
PAUL V. GALVIN LIBRARY
35 WEST 33RD STREET
CHICAGO, IL 60616

APPROVED:

Dean of Engineering Studies

Dean of Cultural Studies

Object.

It is not the expectation of adding materially to the subject matter already in the possession of the instructor of industrial education that has led the author to undertake this work. It is rather that, in his own experience as a teacher, he has felt the lack of standardization, correlation, and progression of the subjects commonly presented and generally recognized as an essential to a pre-vocational or industrial education and has collected in those pages the results of his efforts to re-arrange and unify.

Four distinct and completely outlined courses, from the ninth up to and including the thirteenth year, are herewith submitted. They are designed to meet the needs of all boys in the school systems who are mechanically inclined and it is the author's hope that, if

27467

closely followed, they will prove more efficient than courses chosen at random however excellent the individual texts.

The first outlined is the "General Trade Course" for boys who, in after life, will wish to enter some one of the trades. Upon completion of the work specified it is the author's idea that a diploma should be awarded as in all other courses, but that it should be designated as "non-accredited".

The second is that entitled the "Manual Training Course" for those lads who may, or may not, wish to enter college, but who feel that, whatever may be their after life, a slight general knowledge of the Manual Arts will be of value.

The "Preparatory Architectural" and the "Preparatory Engineering" represent respectively the third and fourth courses outlined and are for those students who intend to pursue a technical education after graduation

from High school.

In regard to the last [illegible] it is important to workers and that, due to the insistent demand of the high [illegible] for better preparation on the part of students entering and graduating from High reading [illegible] is advisable for all the [illegible] schools to make [illegible] advanced credits as possible. It is evident that the time [illegible] possible to give much more attention [illegible] technical subjects of the [illegible] with the result that [illegible] leave those institutions [illegible] domestic life. With this object in view the "Laboratory Equipment" and "Shop Equipment" courses have been held [illegible] years of graduate work.

Believing that [illegible] all-

lustration makes a stronger, more lasting, and more accurate impression upon the mind of the pupil than any written description or explanation could possibly do, the author has used drawings wherever possible and has eliminated the written text. There is a two-fold advantage in this for, without his knowledge, perhaps, the student will attempt to bring his own style to the standard set by the plates which he studies.

The illustrations in Book No.1 of this work are reproductions of drawings made by pupils in the D4A and D5-6M classes conducted by the author and represent what, in his opinion, should be expected of "A class" pupils.

R.A.F.

CONTENTS III

ABSOLUTE VALUE OF COMPLEX QUANTITIES ..... 1 - 30

ADDITION 1

SUBTRACTION 2

MULTIPLICATION 3

DIVISION 4

EXTRACTION OF ROOTS ..... 5 - 8

INVOLUTION 9

EVOLUTION 10

EXPONENTIAL EQUATIONS ..... 11 - 30

LOGARITHMS ..... 31 - 50

DEFINITIONS 31

PROPERTIES OF LOGARITHMS 32

COMMON SYSTEM OF LOGARITHMS 33

USE OF TABLES ..... 34 - 50

LOGARITHMIC COMPUTATION ..... 51 - 60

MULTIPLICATION 51

DIVISION 52

INVOLUTION 53

EVOLUTION 54

COMPOUND INTEREST ..... 55 - 60

ANNUITIES ..... 61 - 70

AMORTIZATION ..... 71 - 80

SINKING FUNDS ..... 81 - 90

TABULAR VIEW OF COMPLETE COURSES.

GENERAL TRADE COURSE.

First Year.

First Semester:-

English
Biology or Botany
Course No.S1 Bench Work (2 Periods Daily)
Course No.D1 Mech Drawing (2 Periods Daily)
Free-hand Dr. (4 Periods Weekly)

Second Semester:-

English
Physiology or Botany
Course No.S2 Bench Work (2 Periods Daily)
Course No.D2. Mech. Drawing (2 Periods Daily)
Free-hand Dr. (4 Periods Weekly)

Second Year.

First Semester:-

English
Advanced Arithmetic (Commercial)
Course No.S3 Wood Turning (2 Periods Daily)
Course No.D3 Mechanical Dr. (2 Periods Daily)
Free-hand Dr. (4 Periods Weekly)

Second Semester:-

English
Advanced Arithmetic (Commercial)
Course No.S4 Pattern Making (2 Periods Daily)
Course No D4 Mech. Drawing (2 Periods Daily)
Free-hand Dr. (4 Periods Weekly)

A Mechanical Course For High Schools.

GENERAL TRADE COURSE (Continued)

Third Year.

First Semester:-

English
Algebra
Course No.35 Forge Shop (2 Periods Daily)
Course No.D5 Mech. Drawing (2 Periods Daily)
Free-hand Dr. (4 Periods Weekly)

Second Semester:-

English
Algebra
Course No.36 Foundry (2 Periods Daily)
Course No.D6 Mech. Drawing (2 Periods Daily)
Free-hand Dr. (4 Periods Weekly)

Fourth Year.

First Semester:-

Geometry
Course No.37 Machine Shop (4 Periods Daily)
Elect One
Chemistry
Physics
American History and Civics
English, French or German.

Second Semester:-

Geometry
Course No.38 Shop (4 Periods Daily)
Continue Elective of First Semester.

A Mechanical Course For High Schools.

GENERAL MACHINE SHOP (3 methods)

Fifth Year.

First Semester:-

Course No.89 Shop (4 Periods 2 day)
Course No.[illegible] Mech. Drawing and Pattern Shop
If Course No.[illegible] (2 periods daily)
Elect from:
Chemistry
Physics
American History and Civics
English, French or German.

Second Semester:-

Course No.89 Continue (4 periods daily)
Course No.[illegible] Construct (4 periods daily)
Continue Elective of First Semester.

NOTE:- In this course, where it is practicable to do so, the pupils should have taught English, Mathematics, Science, Civil Government, and History in classes by themselves or other than those attended by boys and girls and present the subjects in such a way as to have direct application to the future industrial life of the boy. Special short courses should be arranged for, from the subject matter herein prescribed, to accommodate those who, through pressure of circumstances, must begin earning as soon as possible. All these courses should be selected with the idea of it underlying principles rather than the technique as of first importance.



A MECHANICAL COURSE FOR HIGH SCHOOLS
BY ROBERT A. PERKINS.

PLATE NO.	FRAME COLONIAL RESIDENCE for MR. JOHN SMITH SIOUX FALLS	DRAWN BY HAROLD T. SPITZNAGEL
1		S.D. DAK.

A Mechanical Course For High Schools.

MANUAL TRAINING COURSE.

First Year.

First Semester:-

English
Algebra
Physiography
Course No.D1 Mech. Drawing (2 Periods Daily)
Free-hand Dr. (4 Periods Weekly)

Second Semester:-

English
Algebra
Course No.S1 Bench Work (2 Periods Daily)
Free-hand Dr. (4 Periods Weekly)
Physiography

Second Year.

First Semester:-

English
Geometry
History
Course No.D2 Mech. Drawing (2 Periods Daily)
Free-hand Dr. (4 Periods Weekly

Second Semester:-

English
Geometry
History
Course No.S3 Wood Turning (2 Periods Daily)
Free-hand Dr. (4 Periods Weekly)

A Mechanical Course For High Schools.

MANUAL TRAINING COURSE (Continued)

Third Year.

First Semester:-

English
Algebra
Physics
Course No.D3 Mech. Drawing (2 Periods Daily)
Art Work (4 Periods Weekly)

Second Semester:-

English
Algebra
Physics
Course No.S5 Forge Shop (2 Periods Daily)
Art Work (4 Periods Weekly)

Fourth Year.

First Semester:-

English
Solid Geometry
Chemistry
Course No.D4 Mech. Drawing (2 Periods Daily)
Art Work (4 Periods Weekly)

Second Semester:-

English
Trigonometry
Chemistry
Course No.S6 Foundry (2 Periods Daily)
Art Work (4 Periods Weekly)



A MECHANICAL COURSE FOR HIGH SCHOOLS
BY ROBERT A. PERKINS.

PLATE NO.	FRAME COLONIAL RESIDENCE FOR MR JOHN J. MITH SIOUX FALLS SO DAK	DRAWN BY HAROLD A. T. SPITZNAGEL
2		

A Mechanical Course For High Schools.

PREPARATORY ARCHITECTURAL COURSE.

First Year.

First Semester:-

English
Algebra
Greek History
Course No.S1 Bench Work (2 Periods Daily)
Art Work (4 Periods Weekly)

Second Semester:-

English
Algebra
Roman History
Course No.D1 Mech. Drawing (2 Periods Daily)
Art Work (4 Periods Weekly)

Second Year.

First Semester:-

English
Geometry
Course No.S2. Bench Work (2 Periods Daily)
French or German
Art Work (4 Periods Weekly)

Second Semester:-

English
Geometry
Course No.D2 Mech. Drawing (2 Periods Daily)
French or German
Art Work (4 Periods Weekly)

A Mechanical Course For High Schools.

PREPARATORY ARCHITECTURAL COURSE (Continued)

Third Year.

First Semester:-

English
Algebra
Course No.D3 Mechanical Dr. (2 Periods Daily)
French or German
Art Work (4 Periods Weekly)

Second Semester:-

English
College Algebra
Course No.D4 Architectural Drawing (2 PeriodsDaily)
French or German
Art Work (4 Periods Weekly)

Fourth Year.

First Semester:-

English
Trigonometry
Physics
Course No.D5 Architectural Dr. (2 Periods Daily)
Art Work (4 Periods Weekly)

Second Semester:-

English
Trigonometry
Physics
Course No.D6 Architectural Dr. (2 Periods Daily)
Art Work (4 Periods Weekly)

A Mechanical Course For High Schools.

PREPARATORY ARCHITECTURAL COURSE (Continued

Graduate Year.

First Semester:-

Course No.D7
Descriptive Geometry (2 Periods Daily)
Architectural Dr. (4 Periods Daily)
Chemistry (General)
Art Work (4 Periods Weekly)

Second Semester:-

Course No.D8
Descriptive Geom. (2 Periods Daily)
Architectural Dr. (4 Periods Daily)
Chemistry (General).
Art Work (4 Periods Weekly)



A MECHANICAL COURSE FOR HIGH SCHOOLS
BY ROBERT A. PERKINS.

PLATE NO 3	FRAME COLONIAL RESIDENCE for MR JOHN SMITH SIOUX FALLS S.DAK.	DRAWN BY HAROLD T SPITZNAGEL

A Mechanical Course For High Schools.

PREPARATORY ENGINEERING COURSE.

First Year.

First Semester:-

English
Algebra
Greek History
Course No.D1 Mech Drawing (2 Periods Daily)
Free-hand Dr. (4 Periods Weekly)

Second Semester:-
English
Algebra
Roman History
Course No.S1 Bench Work (2 Periods Daily)
Free-hand Dr. (4 Periods Weekly)

Second Year.

First Semester:-

English
Geometry
Course No.D2 Mech. Drawing (2 Periods Daily)
German or French
Free-hand Dr. (4 Periods Weekly)

Second Semester:-

English
Geometry
Course No.S3 Turning & Pattern Making (2 Periods Daily)
German or French
Free-hand Dr. (4 Periods Weekly)

A Mechanical Course For High Schools.

PREPARATORY ENGINEERING COURSE (Continued)

Third Year.

First Semester:-

English
Algebra
Physics
Course No.D3 Mech. Drawing (2 Periods Daily)
German or French

Second Semester:-

English
College Algebra
Physics
Course No.S5 Forge Shop (2 Periods Daily)
German or French

Fourth Year.

First Semester:-

English
Solid Geometry
Chemistry
Course No.D4 Mech. Drawing (2 Periods Daily)
Economics

Second Semester:-

English
Plane Trigonometry
(Note) If the graduate year is taken, Shop S4 will be substituted for Trigonometry in this semester.

A Mechanical Course For High Schools.

PREPARATORY ENGINEERING COURSE (Continued)

Chemistry
Course No.S6 Foundry (2 Periods Daily)
Economics

Graduate Year.

First Semester:-

Descriptive Geom. (2 Periods Daily)
Course No.D5 Mech. Drawing (2 Periods Daily)
Course No.S7 Machine Shop (2 Periods Daily)
Plane Trig. (1 Period Daily)

Second Semester:-

Descriptive Geom. (2 Periods Daily)
Course No.D6 Mech.Drawing (2 Periods Daily)
Course No.S8 Machine Shop (2 Periods Daily)
Analytical Geom. or Scientific
German or French.



A MECHANICAL COURSE FOR HIGH SCHOOLS
BY ROBERT A. PERKINS.

PLATE NO 4	FRAME COLONIAL RESIDENCE for MR. JOHN SMITH SIOUX FALLS SO. DAK.	DRAWN BY HAROLD SPITZNAGEL

A Mechanical Course For High Schools.

-Outline of-

MECHANICAL DRAWING COURSES.

Course D1.

Plates Nos. 1 and 2 in lettering are designed to give the student an idea of the letter and figure forms most commonly employed in practical office work and some facility in their use. Plates Nos. 3,4, and 5 are in geometrical constructions and fill the two-fold purpose of affording exercises in which to become familiar with the use of instruments and of impressing the pupil with the need of accuracy and neatness in his work. The last four plates, Nos. 6,7,8, and 9, are in furniture design and cover the exercises to be executed in shop Course No. B1. Not less than one hundred and fifty words, exclusive of titles and name plates are to accompany each plate. This lettering is to be in explanation of the problems



A MECHANICAL COURSE FOR HIGH SCHOOLS
BY ROBERT A PERKINS

PLATE No. 5

FRANK SCHOLL RESIDENCE
FOR
MR JOHN SMITH
SOUTH PAUL

DRAWN BY HAROLD T

and in answer to the questions accompanying them. This lettering is to be done as home work, upon quarter size plates, and attached by clips to the main plate when it is submitted for correction.

Course D2.

Plate No.1 in line or stipple shading of surfaces, is to be practiced until gradations can be made smoothly. The first turning exercises, of Course No.S3 are designed and rendered in this plate. Plate No.2 in graded washes, is the design of the built-up pulley pattern, pilot wheel, or hand wheel, one of which is to be selected as the last exercise of Course No. S3. (Note:- Cuts of a few of these models made in the author's classes are included in this text) Plate No.3 is the design of the main project for shop Course No.S2 and is to be worked out by the pupil from some cabinet

North Elevation

A MECHANICAL COURSE FOR HIGH SCHOOLS
BY KUBERT A PERKINS

PLATE NO		DRAWN BY
6	FRAME COLONIAL RESIDENCE FOR MR JOHN SMITH SIOUX FALLS	SCALE SQ DAK, SPITZNAGEL

he has seen and wishes to duplicate or it may be an original idea which is acceptable to the instructor. Plates 4 to 9, inclusive, are in orthographic projections, explaining the theory of lines, true length and fore-shortened, development of surfaces, and beginning penetrations. The surfaces are to be rendered in flat washes where specified. The same amount of lettering must accompany each plate in this course as is specified for Course D1.

Course D3.

Plates Nos. 1 and 2 cover the design of the exercises for forge shop S5. and give the student, at the same time, his first experience in the conventions employed in the design of simple steel pieces. Plates Nos. 3 to 9, inclusive, are in penetrations and developments of surfaces, showing traces of intersections, and are to be rendered in washes or in line shading where specified. All developments are to be cut from heavy paper or light sheet

EAST ELEVATION

A MECHANICAL COURSE FOR HIGH SCHOOLS
BY ROBERT A. HERRING

PLATE No. 7

FRAME RESIDENTIAL BUILDING

MR. JOHN SMITH

ISHAWA, IOWA

metal with the area within the line of intersection removed from one surface and the trace of intersection left upon the other. When the two surfaces are placed together in the required position, the pupil will have a mechanical demonstration of the accuracy of his drawing. Lettering requirements are the same as in D1. and D2. At this point the mechanical drawing is divided into the two departments of "Preparatory Engineering" and "Preparatory Architecture"; it being optional with students of the "General Trade" and "Manual Training" Courses which of these they will pursue.

South Elevation

A MECHANICAL COURSE FOR HIGH SCHOOLS
BY ROBERT A PERKINS

PLATE NO		DRAWN BY
8	FRAME COLONIAL RESIDENCE for MR JOHN SMITH SIOUX FALLS SO DAK	HAROLD T SPITZNAGEL

A Mechanical Course For High Schools.

-Outline of-

ARCHITECTURAL DRAWING COURSES.

Course D4A.

Eleven plates in residence design represent the assignment for this course consisting of Plates 1 to 4, floor plans, 5 to 8, the elevations, and 8 to 11, the wall sections and interior and exterior details. An idea of the scope of the course may be obtained by reference to the first twelve plates included herewith.

The object of this course will have been accomplished if the student has acquired a knowledge of the rudiments of building framing, the principles of representation employed in making building plans, and the ability to interpret correctly a set of not too complicated building plans when they are placed before him.



WALL SECTION
THRU EAVES
SCALE-1½" = 1'-0"



SECTION THRU GABLE
SCALE-1½" = 1'-0"



DETAILS OF
DOUBLE-HUNG WINDOWS
SCALE-3" = 1'-0"

DETAILS OF
CASEMENT WINDOWS
SCALE-3" = 1'-0"



DETAIL OF FRONT ENTRANCE
SCALE-¾" = 1'-0"



SECTION OF FRONT ENTRANCE.

A MECHANICAL COURSE FOR HIGH SCHOOLS
BY ROBERT A. PERKINS

PLATE NO. 10	FRAME COLONIAL RESIDENCE for MR. JOHN SMITH, SIOUX FALLS, SO. DAK.	DRAWN BY HAROLD T. STITNAGEL

A Mechanical Course for High Schools.

Lettering is as in the preceding courses.

Course D4A.

Plates 1 to 6, inclusive, in this course deal with the two most used forms of perspective construction, viz. the "Oblique Method" and the "Distance Point Method". Problems involving the perspective of simple combinations of geometrical solids are first employed. These are increased in difficulty as the course progresses, until the final problem, which is the perspective of the reside be design ed in Course D4A and comprises the whole of Plate 7 See Plate No. 7, page [illegible] Lettering as before specified.

Course D4B.

Nine pl tes are included in this course covering the follow g subject matter: First, the shadow of objects in perspective with the rays of light parallel to the picture plane:



NORTH ELEVATION OF DINING ROOM.



FRONT ELEVATION OF CHINA CLOSET



ELEVATION OF MAIN STAIRS
SCALE ¾" = 1'-0"

WARDROBE IN MAIDS ROOM
SCALE ¾" = 1'-0"



PART PLAN OF DINING ROOM.
SCALE ¾" = 1'-0"

PLAN OF STAIRS
SCALE ¾" = 1'-0"



MEDICINE CASE.
SCALE ¾" = 1'-0"

SECTION A A.
SCALE ¾" = 1'-0"

NORTH ELEVATION OF DEN SHOWING BOOKCASES.
SAME CASES ON SOUTH SIDE OF DEN, SIMILAR EXCEPT 10" DEEP.
SCALE ¾" = 1'-0"

SECTION THRU BOOKCASES.



ELEVATION OF LINEN CLOSET.
SCALE ¾" = 1'-0"

A MECHANICAL COURSE FOR HIGH SCHOOLS.
BY ROBERT A. PERKINS.

PLATE NO.		DRAWN BY
11	FRAME COLONIAL RESIDENCE for MR. JOHN SMITH SIOUX FALLS S.D. DAK.	HAROLD T SPITZNAGEL

second, with the source of light in front of the observer; and third, with the source of light behind the observer. Three plates are given to this, the fourth plate consisting of the laying out of shadows and complete rendering of plate No.8, Course D6A. Plates 5 to 8 are given up to shades and shadows in interior perspective and plate No.9 is designed to introduce a few of the principles of reflections.

All shadows are to be laid out with extreme care and the drawings rendered in water color. It is in this and the succeeding courses especially that the value of the four years of art called for in the "Preparatory Architectural Course" is shown, for the beauty of the drawings will be to a great extent dependant upon the ability to use colors effectively. Letter-



FIREPLACE IN LIVING ROOM
SCALE-¾" = 1'-0"



PLAN OF HEARTH



NORTH ELEVATION OF PANTRY



SECTIONAL DETAIL

SECT. PLAN OF PANTRY CASE.



FIREPLACE IN SUN PARLOR
SCALE ¾" = 1'0"

PLAN OF HEARTH



SOUTH ELEVATION OF PANTRY
SCALE ¾" = 1'-0"



ELEVATION OF KITCHEN CASE
SCALE-¾" = 1'-0"

DOOR LIST

NO.	SIZE	STYLE	LOCATION
4	2'-6" × 7'-0" × 1¾	SINGLE PANEL D.S.	KIT. INT. DUTCH DOOR
3	2'-6" × 7'-0" × 1¾	HALF GLASS	REAR ENTRANCE
2	3'-0" × 7'-0" × 1¾	COLONIAL	FRONT ENTRANCE VESTIBULE
1	2'-6" × 7'-0" × 1¾	FIVE CROSS PANEL D.S.	TOILET
3	2'-6" × 7'-0" × 1¾	SINGLE PANEL D.S.	DINING-ROOM PANTRY
2	1'-9" × 7'-0" × 1¾	SINGLE PANEL D.S.	VESTIBULE CLOSET.
1	2'-6" × 7'-0" × 1¾	SINGLE PANEL D.S.	HALL CLOSET
4	2'-6" × 7'-0" × 1¾	FRENCH	LIVING ROOM FRENCH
7	2'-6" × 6'-6" × 1¾	FIVE CROSS PANEL D.S.	UPSTAIRS BED ROOMS
9	2'-6" × 6'-6" × 1¾	FIVE CROSS PANEL D.S.	UPSTAIRS CLOSETS
2	2'-6" × 6'-6" × 1¾	FIVE CROSS PANEL D.S.	LINEN CLOSET
1	2'-6" × 6'-6" × 1¾	FIVE CROSS PANEL D.S.	ATTIC CLOSET
3	2'-6" × 6'-6" × 1¾	FIVE CROSS PANEL D.S.	ATTIC B.R. STORE ROOM

A MECHANICAL COURSE FOR HIGH SCHOOLS
BY ROBERT A. PERKINS

PLATE NO. 12

FRAME COLONIAL RESIDENCE
FOR
MR. JOHN SMITH
SHAKOPEE S.DAK.

DRAWN BY HAROLD T. STITENGER.

ing as in previous courses.

Course D7A.

This course is given up to the study of shades and shadows and is introductory to Course D8A in the same subject. In deriving the lines of shade and of shadow in this preliminary course use is made of plans, elevations, and sections. The first five plates, ranging in difficulty from the derivation of the shade and shadow of the simplest geometrical solids up to those of the more or less complicated architectural details, should give the student's imagination the needed training for taking the short cuts explained in the following course. The last four plates of this course require the laying out of the shade and shadow upon the four elevations of D4A. These are to be rendered in flat washes of water color. Lettering as before specified.



℄ H.P Cylinder

Section A-A.

℄ L.P Cylinder.

PLATE No. 1	ENGINE DESIGNING.	DRAWN BY~BBB
A MECHANICAL COURSE FOR HIGH SCHOOLS BY ROBERT A PERKINS		

A Mechanical Course For High Schools.

Course D8A.

Eight plates in continuation of Course D7A at the completion of which the student is supposed to be able to lay out the shade and shadow of vases, cornices, colums, etc., with but little reference to the plan or sectional views, the points being located upon the lines of shade and shadow directly through a knowledge of the forms of the surfaces producing and receiving the shade and the shadow. Critical cones and many other means which have been devised for expediting the work are explained in detail. Lettering as in other courses.



Section B-B

PLATE No. 2.	ENGINE DESIGNING.	DRAWN BY ~ BBB

A MECHANICAL COURSE FOR HIGH SCHOOLS.
BY ROBERT A. PERKINS.

A Mechanical Course For High Schools.

-Outline of-

PARTIAL COURSE FOR DRAWING.

Course D5.

The first three plates of this course are given to the introduction of the most important problems of pure mechanical drawing. Some of the topics touched upon are: the development of the helix with its application to various types of threads, the types of bolts most used in machine construction, the design of nuts, and the theory of cross spotting. In fact, they furnish the geometrical data necessary to enter upon Course D5. The last five plates of this semester's drawing the outline is developed to isometric projection, and it, as in the case in perspective, begins with the construction of isometrics of simple geometrical solids. As the course progresses the problems are in-



PLATE No. 3.	ENGINE DESIGNING.	DRAWN BY-BBB

A MECHANICAL COURSE FOR HIGH SCHOOLS.
BY ROBERT A. PERKINS.

creased in difficulty until in the last two plates the drawings called for are of rather complicated machine parts. Special attention is to be paid to the lettering plates accompanying drawings.

Course DĒL.

An idea of the quality of draftsmanship that should be expected from the pupil that has reached this point in the "Preparatory Engineering Course", and about the field to be covered by Courses DĒL and DĒL can be obtained by reference to Plates Nos. 1 to 8, inclusive, (pages.....), the work of a student in the author's classes.

The Courses DĒL and DĒL are really one continuous course and provide for the design of one of two problems, either a vertical high steam engine or a gas engine of the four cycle type. The plates may read in the two ways:



Section D-D

Scale ~ 2" = 1."

PLATE No. 4.	ENGINE DESIGNING	DRAWN BY ~ PPP

A MECHANICAL COURSE FOR HIGH SCHOOLS.
BY ROBERT A. PERKINS.

Plates No.1 and No.4, inclusive, cylinder sections; Plates No.5 to No.8, inclusive, details of parts; and Plate No.9, front and side elevation of assembled engine. A tenth plate that may be drawn, in case time is found, is the isometric of the engine, but this course should never be crowded, as extreme neatness and accuracy are much more important in machine design than multiplicity of plates. As it is necessary for the student undertaking either of the above problems to have several plates under construction at the same time, it is the author's plan that no attempt should be made to complete any definite part of the design at the mid-year, but rather, that two credits be given at the end of the year when the nine plates are submitted.

Finally: At the completion of each of the

Relief Valves for Cylinders.



2 Off Complete.

H.P. Piston Head.



1 Off.

Valve Rod Glands



2 Off

Piston Rod Glands



2 Off

H.P Valve and Valve Rod



L.P Piston and Piston Rods



2 Off Piston Rods
1 Off Piston

H.P Piston Rings.



2 Off

L.P Piston Rings



2 Off

L.P Valve and Valve Rod



1 Off Each

Wyper Shaft



1 Off.



1 Off Each

Support for Wyper Shaft



2 Off.

Scale ~ $\frac{1}{2}$ = 1"

PLATE No. 5	ENGINE DESIGNING.	DRAWN BY-BBP
A MECHANICAL COURSE FOR HIGH SCHOOLS. BY ROBERT A PERKINS		

courses in drawing every student, regardless of his grades, should be required to take a thorough examination, of not less than four hours duration, in the theory of the subject covered. In no other way can he be assured that none of the important details have escaped him.


Engine Bed
Cast Iron Support
Column
4"
2'-9"
8"
1'-0"
1'-3"
1 Off.
Swinging Link.
2 Off.
Metal of uniform thickness = 3/8"
1'-2 1/2"
1'-1 1/4"
6 1/2"
9"
2 Off.
3/8" bolt holes.
1/2" bolt holes.
1/8" Rad
2 Off.
Wyper.
1 Off.
Shaft
Symmetrical with respect to axis A-A
Angle of Advance = 21°
℄ Pulley
℄ Journal
℄ Cyl.
℄ Eccentric
Axis A-A
1 Off.
PLATE No 6.
ENGINE DESIGNING
DRAWN BY ~ BBB
A MECHANICAL COURSE FOR HIGH SCHOOL
BY ROBERT A. PERKINS.

A Mechanical Course for High Schools.

-Outline of-

SHOP COURSES.

As a prerequisite to the shop courses of the High school, the boy should have received two years of wood work in the grades, the minimum time allowance for which was fifty-four hours a year. During that time careful instruction should have been received in the care of tools, characteristics of woods commonly used in construction, joinery, and the use of hot glue. The courses, hereinafter outlined, should not be attempted without arranging for this preliminary work.

Course S1.

Beginning with the first year in High school, all the exercises are in practical construction and are of a progressive nature, making it possible for the student to see by a

A Mechanical Course for High School.

is necessary to solve a problem in order that he may have sufficient skill successfully to attack the next. With the kind of drill which would be already familiar, for he has made the drawings in the drafting class which precede the shop course. This study applies to the shop courses without exception. Whatever elective designs are offered, the pupil should be urged to decide upon the one he will wish to construct before starting upon his drawing, for only in this way will he receive the full benefit of the course he will elect. Under no circumstances should shop models be permitted upon exercises for which complete drawings have not been made.

These exercises, as explained in Course II, constitute the principal work in this class. Whether half or all of the pupil's time is given to particular exercises should depend upon the


Valve Rod Links
XLP
XHP
2 Off
Note; X=1/4" on H.P. Valve Rod Link
X=1/2" on L.P. Valve Rod Link
Connecting Rods
2 Off
Wyper
2 Off
Drag Link
2 Off
Return Lever
1 Off.
Locking Gear
1 Off
Reversing Handle
Wood Handle
1 Off
Reversing Shaft
1/4" Keyway
1 Off
Eccentric Strap
2 Off
℄ Drag Link
℄s Swinging Links
℄ Drag Link
Scale 6"=12"
Note: On L.P. Cylinder Eccentric Strap
A=4 1/8" B=4 1/8"
On H.P. Cylinder Eccentric Strap
A=4 1/8" B=5 1/8"
Eccentric Strap symmetrical with respect to axis X-Y. Eccentricity=1/16"
PLATE No. 7
ENGINE DESIGNING.
DRAWN BY-BBB
A MECHANICAL COURSE FOR HIGH SCHOOL
BY ROBERT A. PERKINS

great extent upon the instructor's estimate of the individual pupil's strength and ability.

Course S2.

This is a continuation of Course S1., the exercises, however, being more difficult, the grade of workmanship insisted upon of higher quality, and especial attention being given to staining, filling, varnishing, etc. Two exercises only are required for credits, one from the designs of Course D1. and one the cabinet designed in D2., Plate No.5.

Course S3.

At this time a beginning is made in wood turning, the exercises consisting of six spindles, one piece for chuck turning, and one built-up pulley pattern. Alternative exercises are offered which may be used at the discretion of the supervisor. The author has found that it adds interest to this work to


Valve Gear
Front Elevation
Side Elevation
2'-9⅞"
1'-7⅞"
6"
1'-1⅜"
2'-0"
⅝"
6"
3'-0
2'-9"
1'-8" app
4'-5⅞" app
2'-9⅞"
2'-9"
2 5⅞
Scale~3"=12"
PLATE No 8.
ENGINE DESIGNING.
DRAWN BY~BBB.
A MECHANICAL COURSE FOR HIGH SCHOOLS
BY ROBERT A. PERKINS.

allow the pupil to use a light and dark colored wood in building up the exercises. Some of the results obtained will be seen by reference to the cuts on pages .
The first two plates of D2 call for the designs here required. A high shellaced finish is expected on each exercise submitted for credit.

Course S4.

This is a continuation of Course S3 and provides for the making of patterns and core boxes for the gas engine and marine type steam engine for which the drawings are made in Courses D5M and D6M. Unlike the preceding shops, this and the succeeding courses call for the combined efforts of the class upon a unit product. An added value, educationally, is the result, for the individual can see how essential it is that his work be done with accuracy in order



that it fit in with that of others. The supervisor, however, will be called upon to give even more careful attention to this department for the assignment of each student being different, the remainder of the class must be kept informed as to what is being done, what difficulties are presented, and how they are to be overcome. While the text explains the construction of each pattern, it will be evident that only the instructor can see to it that each individual earns his credit, for no two patterns have, even approximately, the same difficulties.

Course S5.

At this point in the shop schedule forging is introduced. Logically, of course, the foundry should follow pattern making, but for two reasons the author has reversed this order. The first of these reasons is that in

A Machine Tool Course for High School [illegible].

[illegible] school system [illegible] those [illegible] [illegible] [illegible] skill, in all probability, to [illegible] [illegible] [illegible] vide space [illegible] [illegible] [illegible] [illegible] [illegible] [illegible] for the foundry; and then [illegible], [illegible] [illegible] [illegible] [illegible] [illegible] [illegible]

Shop Copy
Not

A Mechanical Course For High Schools.

Course S6.

In the foundry, commencing with bench work, or the molding and casting of the simple turned pieces of S3., the difficulty of the work is increased as the course progresses by the use of the patterns of S3.; and finally, by those of S4, is made to introduce the baked sand core, the flask with false checks, and the heavy floor work. Light work will also be done in brass and white metal.

Course S7.

The finishing of the castings and forgings made in S6 and S5, respectively, and in advanced shop S8, constitutes the work of this shop course.

A few simple exercises in chipping and filing are first required after which the student takes up, in succession, exercises which require him to use the lathe, drill press,

A Mechanic's Course in Machine Shop Practice.

shops, planers, grinding machine, [illegible] machine, and many other appliances. Course 350 in machine shop work is the same as that of 87 with the addition, however, of practical exercises in tool making.

Course 90.

This is an advanced course in 34, 35, 36, or 3 , and is open to only the students in the "General Trade Course".

Courses 99 and 87.

These are offered only in the "General Trade Course" and are truly vocational in their scope. The courses offered are "Carpentry", "Automobile Construction", "Sheet Metal Working", "Steam Fitting", "Heating and Ventilation", and "Electric Wiring".

In conclusion it may be said that all of the courses have proved still further the utility

A MECHANIC'S LIBRARY
EX. No.2
SHOP COURSE No.3

A Mechanical Course For High Schools.

of product and a quality of workmanship that will require the student of average ability to give his undivided attention to the work if he is to end the semester unembarrassed.

In no other way than by requiring a strict discipline and a product of which the student and the school alike may be proud, can the course of the pre-vocational type be placed upon the same high plane that is occupied by the other departments of education.

Too often the "Last Chance" of those who are simply "going through" high school, the Manual Training Department has provided "busy-work" for which credit was given and which commanded the respect of no one, least of all the students themselves. It is the author's sincere hope that no such criticism can be made of the work as herein outlined

[illegible]

Introduction 1

Background 2

Methodology 5

Findings 8

Conclusion 12

Bibliography 15



Plan View.





Front View.
Sectional Elevation.



Profile
Sectional Elevation.

A · Sewing · Table.

WORKING DRAWINGS · SHOWING · PLAN, FRONT, AND · SIDE VIEWS; ALSO · ISOMETRIC · OF · PROBLEM. SCALE: 3" = 1'-0".

A MECHANICAL COURSE FOR HIGH SCHOOLS.
By Robert A. Perkins.

Frontis-piece · by · R.A.Perkins.	Mechanical Drawing. · Course D1 ·

A Mechanical Course To Match Schools.

MECHANICAL DRAWING.

Course D1.

DEFINITIONS:-

Mechanical Drawing is the graphical representation of objects, problems, or projects upon plane surfaces by the use of instruments. In this respect it differs from the pictorial form of representation, which depends upon the hand and eye alone and seeks not that extreme accuracy so much as for proportion and grace of outline and the appearing of texture or surface.

Descriptive Geometry is the science of drafting all that flows, applies and all the theory of projective drawing of whatever kind. The three forms of projection presented in the following text are:

Orthographic Projection, or
Perpendicular projection.

Perspective or Converging Projection

Single Plane Projection, or
Isometric Projection.

From the foregoing definitions, it will be evident that Descriptive Geometry and Mechanical Drawing bear the same relation to each other as do theory and practice. Either is of but little value without the other.

Drafting Instruments are mechanically constructed devices by means of which precise projections may be constructed.

A book might be written with Drafting Instruments as its subject, explaining the innumerable types that have been invented to fulfill the regular and special requirements of the drafting room. For this course, however, a brief space will suffice to give a list of the tools required, to present an en-



A·MECHANICAL·COURSE·FOR·HIGH·SCHOOLS·

PLATE A	MECHANICAL DRAWING·	BY ROB'T.A. PERKINS

T- SQUARE - AND - TRIANGLES.

Fig A shows a triangle whose angles are 30 degrees, 60 degrees, and 90 degrees Lines a-a indicate the parallels that are drawn at 60° and a-b those at 90° to the horizontal edge of the T square C, by this triangle. Two other positions of this thirty or sixty degree triangle are shown at A1. and A2.

Fig. B shows what is known as the 45 degree triangle and lines b-b and a-b represent two of the sets of lines that may be drawn by its use.

Fig. C and Fig. C1 show two positions of the T square. This should always be used with the head at the left edge of the board as indicated, the triangles and pen to be guided only by the upper edge of the blade.

Figs. A1-B1 and A2-B2 indicate how the triangles may be used in combination to produce other angles, such as e-e at 75° and f-f at 15° to the horizontal. Other angles, such as 22½°, 37½° etc, may be obtained by bi-secting either the angles themselves or their combinations.

Practice Exercise:

From a point on a horizontal line, draw all the divergent lines possible with the 45° triangle and the 30° triangle indicating the number of degrees included between adjacent lines. Do the same exercise at another point using the triangles in combination, instead of singly.

A Mechanical Course For High Schools.

planation of the , and to show how they should be used and cared for.

A medium priced set of instruments is best suited to High school work; for, owing to carelessness and inexperience on the part of the students, loss of parts is certain to occur and accidents are frequent. The list required is as follows:

One 30 inch T-square; one 8 inch, sixty degree triangle; and one 8 inch, forty-five degree triangle, all shown in Plate I., with explanations accompanying; two small French curves and one 12 inch Architect's scale of triangular cross section, having 1 8 inch, 1/4 inch, 3/16 inch, 3 8 inch, 1 2 inch, 1 inch, 3/4 inch, 1 1/2 inch, 3 inch, 1 inch, and 12 inch scales per foot, shown and explained in Plate I.; and a set of drafting instru-



FIG. 1

FIG. 2

A MECHANICAL COURSE FOR HIGH SCHOOLS.		
PLATE B.	MECHANICAL DRAWING.	BY ROBT A PERKINS

Two of the many forms of irregular or French curve are shown in Fig 1 A and B. Curves similar to these will be sufficient for the work of this course No drafting instrument will be found that requires more care, patience, and practice to use with skill than does this.

In Fig. 2 points 1 to 24 inclusive are those determining an ellipse and these will be taken to illustrate the manner in which the curve is used in drawing. One portion of the ellipse will be drawn with B (from pt. 7 to pt. 13) and another with A (from pt. 19 to pt. 1) to show that the latter is more practicable in this particular example. To use the curves the following rules should be borne in mind:- 1ST Place so as to include as many points as possible. 2ND Draw line in pencil through these points. 3RD Find a part of French curve which will include two points through which line has already been drawn, and several additional points. 4TH Again draw in pencil starting with overlapping portion. 5TH Continue process 'till all the points are connected. 6TH In inking use but little ink in pen and draw only one-half of portions which overlap with each consecutive position of the French curve.

ONE FOOT IS INDICATED THUS 1

FIG. 3

ONE INCH IS INDICATED THUS. 1"

In Fig. 3 one face of the architects scale is shown and, if the explanation here given is understood, the remaining two sets can be used without difficulty. Scales were designed in order that drawings of large projects might be accurately made in a small space with every part in the same proportion and relation to every other part that must exist in the completed structure It will be evident then that the larger the scale chosen the more nearly actual size the drawing will be and the more detail will be shown. Referring now to the figure it will be seen 1ST That to the left of zero in the 1" and in the ¼" scales is one unit divided into twelve equal parts each of which represents one inch to that scale; 2ND That to the right of zero in the ½" scale is a ½" unit similarly divided; 3RD That one actual foot equals twelve feet to a scale of 1"=1'-0"; twenty-four feet to a scale of ½"=1'-0", and forty-eight feet to a scale of ¼"=1'-0"; and 4TH That readings must be taken with 0 for the initial or starting point in order that figures of scale may give the correct indication.

ments similar to that pictured in Plate 3.

Reference now to the latter article, will show that in figures one to six, inclusive, certain letters of reference are used to indicate those points to which particular attention should be given. These will now be employed in alphabetical order.

"A" Pencil attachment for compass.

The leg of the compass which received the various attachments is provided with a joint just above "e", which the head of the screw is shown. This allows the attachments to be swung to a small position as will bring the pencil or pen point perpendicular to the paper with but very small pressure. This adjustment is necessary, if good results are to be obtained. The arrow at "A" and the dotted line at the left indicate the direction and range of the pen.

"a" In all the figures, this point is a milled head set screw.

The turning of this milled head causes pressure to be exerted upon the pencil from the various attachments, thus clamping them in the desired position or allowing of their adjustment.



FIG. 1





FIG. 3



FIG. 4



FIG. 5

FIG. 2



FIG. 6

Screw Driver and Point Holder

Fig. 1 shows large compass with A, pencil, B, extension bar, C, divider point, and D, pen, attachments; Fig. 2 represents the drafting pen; Fig's 3, 4, and 5 give the three bow instruments viz: the pencil, divider, and pen, and Fig. 6 shows large dividers.

The Richter type of instrument is here shown but the explanation, given on the adjoining page of the text, will be found to apply equally well to any other one of the many types in use.

A MECHANICAL COURSE FOR HIGH SCHOOLS.		
PLATE C	MECHANICAL DRAWING.	BY ROBT. A. PERKINS

A Mechanical Compass For High Schools.

"D" Extension-bar attachment for compasses.

This bar practically doubles the length of the legs of the compass and thus makes possible the drawing of much larger circles. It will be seen that the bar is provided with a hinge joint, which answers the same purpose as that described above.

"b" Milled heads and screws.

These are used for making delicate adjustments, such as bringing the point of line to be drawn, as in the case of the pens, or regulating the exact distance between the points of the dividers, as in the case of fig. 3.

Caution:- Never exert a pow er upon any of the heads. The threads of the screws are very fine and may be stripped.

"c" Dividing-leg attachment for pencils.

When this is in place it appears as shown in fig. 1 at b. It is used for the same purpose, viz. to transfer distances from line to line or from place to place, [illegible] divor like fig. 3 described and for small parts by hand.

"c" Pen attachment for 3 legs
See "c" for explanation.

A Logical Analysis of Mathematics.

"A" Logical Analysis.

This differs from "A" in that [illegible]

"B" This is [illegible] the [illegible]

of [illegible] the [illegible] of [illegible]

the [illegible] [illegible]. In [illegible], [illegible]

[illegible] [illegible] [illegible] [illegible]

[illegible].

"C" [illegible] [illegible] [illegible].

This [illegible] [illegible] [illegible] [illegible]

which [illegible] [illegible] [illegible] [illegible].

"D" [illegible] [illegible] [illegible].

[illegible] [illegible] [illegible] [illegible]

[illegible] [illegible] [illegible] [illegible]

[illegible] [illegible].

"E" [illegible] [illegible].

[illegible] [illegible] [illegible] [illegible]

[illegible] [illegible] [illegible] [illegible].

A Mechanical Code [illegible] High School.

"I" [illegible] instruments, [illegible] Design the letter "C" in a position [illegible] tion, relative to the [illegible] long drum.

"J" [illegible]

[illegible] hand-hand scale, [illegible] tance between [illegible]

CAUTION :- [illegible] left [illegible] while [illegible] under like [illegible] "J" [illegible] must [illegible] form [illegible] scale.

"K" Points of [illegible]

[illegible] are [illegible] otherwise [illegible]

A Mechanical Device for Writing Shorthand.

"a" Combined right- and left-hand screws.

In some designs, a right-hand thread alone is used, but in that case, the pitch of the thread is placed outside the row of holes, instead of running the screw, through upon it and forces the nuts together.

"b" Points of view.

These should always be kept clearly in view, for it is useless to attempt to obtain satisfactory results by a confusion of the different.

In using the machine (see Fig 2,

First:- Write, with the stylus, the letter "b" in the middle division of the paper.

Second:- Note that the letter "b" will not be distorted, whatever its position in the width of the paper, without shifting the position of the nuts.

Third:- On the right margin of the paper, on the position of the letter "b", draw several short lines, varying in length from 1 to 4 inches, and note the distance between the "b" and the first line.

Fourth:- Take the bottom bar, which is provided with a scale of inches, and adjust the nuts so that the distance between the first line and the letter "b" is the same as the distance between the letter "b" and the first line. Then tighten the nuts, and it will be found that the letter "b" will be in the middle of the width of the paper, and will be necessary to re-write it.

A Mechanical C[illegible] For High Schools.

CAUTION:- Remember that blots are caused by filling the pen too full, by attempting to draw too deep a stroke, or by [illegible] pen point to rub the pen point [illegible] with the nails, by dropping the pen, or by holding pen near when attempting to blow [illegible] while [illegible] the paper.

Fifth:- Rule the vertical and ruled lines, [illegible] pens without metal above.

TUTE:- When circles or ovals [illegible] are taught to straight lines, [illegible] be able to [illegible], [illegible] slightly [illegible] by the case of the [illegible], but the circle is [illegible]

Sixth:- Often pen [illegible] every few minutes.

"v" Pen Manfle:-

Never buy a pen with [illegible] handle. Even those [illegible] are unsatisfactory, as they [illegible] [illegible] broken. A [illegible] altogether the most satisfactory.

In general, it may be said that one can judge by the care he gives his instruments, [illegible] of a business man's character.

A Mechanical Cure for Thin Skin Sensibility.

If they be kept polished, by rubbing, and in a moist case; if the hand of the sculptor is not loosened, or the blade nicked, because of particlesemore; if the curves and diameters are not warped from the true, and whole they have been put away; and if the scale is kept clean so that dirt cannot lay the line of [illegible] tables, then the standard will [illegible] yield results. On the other hand, [illegible] and rough treatment of the hold [illegible] tools will be certain to yield [illegible] worthless [illegible].

Details:- See [illegible] "Mech-I-Lu" [illegible], for all the details covered. This shows, with [illegible] the proper [illegible] of the [illegible] of the [illegible].

Because:- The [illegible] "Mechanical" [illegible] all the known [illegible] [illegible] the [illegible] [illegible]. [illegible] use the [illegible] [illegible] [illegible], [illegible] [illegible] [illegible] [illegible] [illegible].

A Lecht ficil Cou[illegible] For Mich Schools.

Pencil to Use:- Use a small hard lead, as the large sizes are difficult to [illegible] Never get to [illegible] of the [illegible]-square, when it is worn near the lower length of the plate.

Ink:- Diguid a black and carbon [illegible] proof inks, but these only, are to be used. Turn not in the [illegible] filling the pen, but [illegible] with a camel's hair pencil, as the ink evapor[illegible] rapidly and becomes too thick to flow freely from the pen. Accidents [illegible] will be [illegible] by following this recommendation.

Paper:- A "[illegible]" sheets of fine-surfaced white paper are to be used when [illegible] this course, unless otherwise specified, the board will be furnished on [illegible].

Lettering Pens:- In the [illegible] of work, [illegible] the [illegible] and [illegible] pen [illegible] [illegible] [illegible]

A Mechanical Course For High School Us.

RULES TO BE OBSERVED
in the
DRAWING Room.

I-

Always wash your hands before each drawing period, "the first day excepted."

II-

Be sure that your T-square, triangles, and drawing board are clean.

III-

Draw lightly. A heavy pencil line scarves the surface of the paper and makes erasure impossible.

IV-

Never be satisfied with a line that is partially erased. If it is necessary to erase it at all, remove it entirely.

V-

Never use ink, colored pencils, sharp erasers, or tracing cloth in making a blue print of these rules or the drawings.

VI-

Never lay in a pile of blue prints, but the back of your drawing, when it is taken from the hill.

A Mechanical Co[illegible] For Fiction Writers.

VII-

Do not try to hurry [illegible] e the [illegible] will mean establishment.

VIII-

Never let a chap go by [illegible] understand. If he [illegible] understand the [illegible] spect your [illegible]

IX-

Learn to discriminate between "[illegible] help" and "[illegible]." The [illegible] upon occasions [illegible] and the necessity of [illegible] tor is stealing [illegible] ability of the one who [illegible]

X-

Do not [illegible] would [illegible] ed when [illegible] ro[illegible]

The [illegible] an way be [illegible]

First: [illegible]

A Model Local Co[illegible] T. High Sch[illegible] ..

[illegible] ere[illegible]; [illegible], [illegible]; fourth, [illegible]; fifth, mathematical [illegible]. Each [illegible] the utmost [illegible] the "[illegible]" [illegible] [illegible]. Provisions [illegible] [illegible] [illegible]

THE FOLLOWING ALPHABETS, EITHER VERTICAL OR AT 75 DEGREES, ARE USED IN COMMERCIAL PRACTICE.

1234567890 ½ ⅛

ABCDEFGHIJKLMNOPQRS
TUVWXYZ.

abcdefghijklmnopqrstuvwxyz.

1234567890 ½ ⅛.

ABCDEFGHIJKLMNOPQ
RSTUVWXYZ.

abcdefghijklmnopqrstuvwxyz.

ABCDEFG
HIJKLMNOPQ
·RSTUVWXYZ·
1234567890

THE · ARCHITECTURAL · STYLE.

ABCDEFGHIJKLMNOPQRSTUVWXYZ

1234567890 ¼ ¾.

abcdefghijklmnopqrstuvwxyz.

I · AM · ONLY · A · PIECE · OF · WORK.
AFTER · I · LEAVE · YOUR · HANDS
YOU · MAY · NEVER · SEE · ME · AGAIN.
PEOPLE · LOOKING · AT · ME, HOW-
EVER, WILL · SEE · YOU · AND, SO · FAR
AS · THEY · ARE · CONCERNED,
I'LL · BE · YOU.
IF · I · AM · SHABBY · AND · POORLY · MADE · I · WILL · GET · INTO · BAD
COMPANY.
IF · I · AM · WELL · MADE · I · WILL
GET · INTO · GOOD · COMPANY · AND
HELP · TO · KEEP · UP · THE · STANDARD.
PUT · INTO · ME · YOUR · BEST
SO · THAT · I · MAY · GO · THE · WAY
OF · ALL · GOOD · WORK · AND · SAY
TO · ALL · THE · WORLD · THAT,
"I · STAND · FOR · A · WORKMAN · WHO
NEEDETH · NOT · TO · BE · ASHAMED."

WILLIAM CHANDLER SMITH.

A MECHANICAL COURSE FOR HIGH SCHOOLS		
PLATE D.	MECHANICAL DRAWING	BY ROBT A. PERKINS

A Weekly Serial Competition.

beginning which the Editor has pleasure
to introduce to the notice of his
numerous readers.

DIRECTIONS.

The "D" Prize, of the value of
[illegible] has been designed by [illegible]. The Editor, however, sets the whole week's Competition, and Prize No. 1 will consist of the Publication in this paper of The "D" for the following week.

RULES:-

1st. Any one may enter the Competition.

2nd. Divide the [illegible] into [illegible].

3rd. [illegible]

Competitors to state [illegible]

Coal [illegible] ...../10"
Wood [illegible] ...../10"
Wood and Coal [illegible] ...../10"

Types of Lines to be Used.



Fig. 1



Fig 3



Fig. 2



Fig. 4

Explanation.

Although some freedom is exercised as to the weight and style of line selected for the various phases of the work, still, by following the instructions here given, the pupil will readily understand whatever system he is called upon to use.

Fig. 1. Square block with square hole therein. Fig. 2. Round block with concentric round hole. Fig. 3. Plan, or top, view of Fig. 1 placed above Fig. 2 Fig 4. Isometric drawing showing same condition as exists in Fig. 3. These illustrate the use of lines A·A to E·E and it will be noted:— 1st That the rays of light, which illuminate all the views of an object, come at 45° L across the plate; 2nd That A·A lines are used toward the light, where two light surfaces intersect, and that B·B lines are used away from the light, where a light surface intersects one in shade; 3rd That C·C lines indicate the position of edges concealed by intervening surfaces; 4th That D·D lines connect different views of the same object, and that E·E lines, with arrows F, (never G) are used to show dimensions.

A·Mechanical·Course·For High·Schools.		
Plate E.	Mechanical Drawing.	By Robt A Perrin

A Mechanical Lettering Triangle.

75 degree Upper Case.....3/16"
75 degree Lower Case.....3/16" and 1/8"
Block Letters.....5/32"
Small Arch'l Capitals.....1/8"
Arch'l Caps. & Figs.....1/16"
Arch't Lower Case.....2/16" and 1/8"

The space between the lines of both kinds is to be made 1/2 of height of capitals of the group or equal to that of the small lower case letters, such as "a","c", etc.

The distance between the groups is to be determined by eye to give the best appearance as that of Block "L".

4th. In the left hand of plate, carefully pencil the letters, when they have been approved by the teacher, ink them in. Make them, as far as possible, by a series of single strokes and reduce the lines of double as feasible. Already have a skeleton of the letters, and the combination of circles by which it is acquired, so that it looks like much time we have in it.

5th. In the right hand of the plate, reproduce the example, while the pencil lines for the first letters of each kind, of both the horizontal. The T, L, H, and the small, be constructed with the T and the L in both cases.

4th. If the first effort is unsatisfactory, repeat several times if necessary.

Plate No.2.

For the second plate, the author has chosen a few lines from the writing of William Chandler Smith, which appeal to him as particularly appropriate for a course of this nature. Surely, with this as an ideal, there would be few failures in any field of endeavor.

INSTRUCTIONS:-

1st. Draw margins and divide plate as in Plate No.1.

2nd. Rule plate, with [illegible] 1/2", and lower space 3/32". The space between lines of lettering to be 3/8".

3rd. Pencil in the first half of plate in either the vertical or 75 degree slant of capital letters and ink with ei[illegible] as in previous plate.

4th. Repeat the lettering in the [illegible] half of plate, and [illegible] the first word in each line, [illegible]



PLATES NOS. 1, 2, AND 3.

PLATES NOS. 1 AND 2. *These plates are in lettering and the specifications for them will be found on the preceding page of the text.*

PLATE NO. 3. *The accompanying figure indicates the manner in which the plate is to be planned to receive the first four problems of course D1.*

PROB. 1 Given:– Line MI [M. 7½"D-1½"R ⅝ I 4¾"D-9½R], point A. on MI. 2" from the lower end, and E. 3"D-5¾"R.

Required:– The construction of the perpendicular bisector of MI and of perpendiculars to MI from points A, E, and I

PROB. 2 Given:– Any two lines A and B, angle abc, and angle def. x 15¾"D-3½"R

Req:– The construction of three triangles with sides A and B; one with acute angle abc, one with obtuse angle def, and one with a right angle included.

PROB. 3. Given:– Line AB and points C, D, and E. [A. 6"D-13½"R, B. 5"D-21"R], C. 3½"D-16"R, D. 4½"D-16"R, ⅝ E 6½"D-16"R.

Req:– A parallel to the line AB through C, D, and E. constructed by a different method in each case.

PROB. 4. Given:– Line AB. [A 15"D-13¾"R ⅝ B. 13½"D-21"R]

Req:– The division of AB into seven equal parts by means of parallels. Check results.

NOTE: For detailed instructions, for solving the problems of this and all succeeding plates, see the text accompanying them.

A·MECHANICAL·COURSE·FOR HIGH·SCHOOLS		
PLATE F	MECHANICAL DRAWING·D1·	BY ROBT A. PERKINS

intersection may be correct.

5th. If the first effort is unsatisfactory, repeat any [illegible], if necessary.

6th. Design [illegible] which may be used, with slight variation, [illegible] entire [illegible] place in the [illegible] illustrated in plate "C".

Plate No.3.

Referring now to plate "C", [illegible] given lines and [illegible] sheet [illegible] for plate No.3.

INSTRUMENTS:- [illegible]

1st. Draw the lines [illegible] A and B. Do not alter [illegible] in this or succeeding [illegible] Plate 1.

2nd. Re[illegible] thoroughly [illegible].

3rd. Solve [illegible] as follows: With [illegible] and [illegible] [illegible] [illegible]

A Mechanical Co[illegible] High Grade.

[illegible] ber 3 and one [illegible] of A which will
number 4. With C as a centre [illegible] -
dent radius [illegible] m 3-4, [illegible] above
and below the line 1-2. With [illegible] the
the same radius, [illegible] -
first drawn in points 3 and 5. [illegible] C.
If the work has been correctly done, this line
will pass through [illegible] -
dicular with the point A.

5th. With D as a centre [illegible] -
what greater than the [illegible] to 1-2,
draw an arc cutting [illegible] 7 [illegible]. With
7 as a centre [illegible] -
half 7-8, [illegible] With C
as a centre [illegible] -
pass [illegible] the 7 [illegible] -
ber 6 to cut [illegible], and [illegible] 8-9,
which will be the [illegible] -
2 to 11.

6th. Assume any [illegible] -
tance above the [illegible] I.
With 12-I as a radius, [illegible] cutting
the line 11 in [illegible]. Join 10-11 and
a line to cut the [illegible] -
point 12. Line 12-I is the required [illegible] -
dicular to the [illegible] I.

NOTE:- In drawing all [illegible] -
plate 2, all construction [illegible] shown
in dotted red lines, as indicated [illegible], and all
given and required [illegible] -
shown [illegible]. [illegible] -
curves.

A Mechanical [illegible]

QUESTIONS:-

I-

What suggestions can you make as to practical and theoretical methods of teaching problems in perpendicular planes ?

II-

What instruments are used by draftsmen and engineers for the construction of curves of double curvature?

INSTRUCTIONS:- Problem 2.

1st. Draw the lines A B.

2nd. Read the [illegible] which they are theoretically in error.

3rd. Letter the ends of the lines A, B, C and D.

4th. With B as a centre, [illegible] setting the [illegible] on [illegible], respectively.

5th. With [illegible] and [illegible] as centres, [illegible] and [illegible] to each end of the line [illegible].

6th. With [illegible], repeat [illegible] to the end, just [illegible], [illegible] distance [illegible] to [illegible].

7th. Through A, [illegible] the end [illegible] it [illegible] A.

A Mechanical Correspondence Problem.

Sir, I [illegible] a solicitor, and [illegible] a re-
[illegible] is [illegible] and [illegible], in-
[illegible] the same.

Sir, In the event of [illegible] require
[illegible] Yours truly,

Sir, [illegible] Yours truly,

Sir, [illegible] Yours truly,

WOULD IT BE:-

I-

[illegible]

II-

[illegible]

III-

[illegible]

ANSWER:- [illegible]

A. [illegible]

A Mechanical [illegible]

points C, [illegible] and D.

[illegible]

[illegible]. Draw [illegible] C, extending [illegible] parallel.

4th. Transfer [illegible] D (as in paragraph [illegible]), [illegible] C, the point C [illegible] D a [illegible] C.

5th. For [illegible], take this [illegible], which is [illegible] C, equal to [illegible].

6th. To establish [illegible] through [illegible] D, [illegible] at D and at [illegible] the line A-B, [illegible] at that point, [illegible] of 4, numbering [illegible] the line 3on [illegible] parallel. For [illegible] line also equal to A-B.

7th. [illegible] place [illegible] modify [illegible] with A-B [illegible] tion, place [illegible] of [illegible] which becomes [illegible] position. [illegible] angle firmly in position, [illegible] it until [illegible] point 1. This line [illegible], through

E,will be the required parallel through this point.

QUESTIONS:-

I-

Where are parallels found in construction work? Mention several important instances.

II-

How do builders and engineers check their accuracy?

III-

Would figures composed of two pairs of parallels have rigidity?

IV-

Mention a few mechanical devices you have seen that prove the correctness of your last answer?

INSTRUCTIONS:- Problem 4.

1st. Draw the line A.B.

2nd. Read the requirements carefully.

3rd. Draw a line of indefinite length extending from A in the general direction of B and at any convenient angle to A.B.

4th. On this line, beginning at A, lay out any convenient length seven times, numbering the points from 1 to 7

A Mechanical Course For High Schools.

5th. Draw the line 7-B and parallel to this through the remaining six points, draw lines intersecting A-B. These points of intersection will divide the line A-B into the required seven equal parts.

6th. For the check required, Draw another line from A, laying off upon it seven equal lengths, slightly different from those in the first part of the problem. Construct the parallels through the points on this line by one of the methods of problem 3 not used in the first part of Prob. 4 The parallels, thus constructed, should pass exactly through the points on A-B determined by the first method.

QUESTION:

I-

What advantage has this method of dividing a line into any required number of equal parts over that of trial or of measuring its length and, after computing the length of the required parts, laying these out upon the line?

Plate No.4.

INSTRUCTIONS: Problem 5.

1st. Draw margins and divide plate as indicated in Plate 3., Fig.1.

2nd. Locate the points (a) and (b) and draw the line ab.



FIG.1



FIG.2

PLATES No.4 AND No.5 D.1

PLATE No.4 *See FIG.1 for arrangement of problems.*

PROB.5 Given:– Two lines, a-b and b-c, with the length ratio of 3:4. Point a[3"R-8¾"D] and b[5¾"R-9½"]

Req:– A right triangle a-b-c; a square constructed on a-b divided into 9 equal small squares; a square constructed on b-c divided into 16 equal squares; and a square upon c-a divided into 25 equal small squares.

PROB.6 Given:– Two circles of 5" diam. with centers located at 20"R-4⅜"D and 14½"R-4⅝"D, the horizontal and vertical diameters of the left circle being drawn.

Req:– The subdivision of the angles A,B,C, and D into 2,3,6, and 8 equal angles respectively. By the use of the various angles, thus determined, it is also required that an inscribed equilateral triangle, square, hexagon, and octagon be constructed in the second given circle.

PROB.7 Given:– Line a-b 1¾" long. a 16¼"R-15°D, b 18"R-15°D.

Req:– The construction of a pentagon, hexagon, heptagon, octagon, and decagon upon a-b as one side.

PLATE No.5 *This plate is to be divided in the same manner as Plate 3 and is to receive Problems 8,9,10, and 11. FIG.2 shows what is given in Prob.9 with letters and figures of reference. For problems, instructions, and questions see text.*

A·MECHANICAL·COURSE·FOR HIGH·SCHOOLS		
PLATE G.	GEOMETRICAL CONSTRUCTION	BY ROBERT A. PERKINS

A Mechanical Construction for High School.

3rd. Describe the [illegible] a-b and construct the right triangle a-b-c, making b-c perpendicular to a-b. (See problem 1, plate C)

4th. Construct squares upon each side and sub-divide each of them as indicated in the requirements. (In constructing and dividing squares, use methods of problem 1, Plate C and problem 1, Plate C.)

QUESTIONS:

I-

What name is given to the longest side of a right triangle?

II-

What relationship exists between the small squares of the figure just constructed, first as to size and then as to number on each of the three sides?

III-

Does this relationship exist for all right triangles?

IV-

How may the simple method [illegible] be used to check the accuracy of [illegible] corners or other squares?

(Suggestion: Construct a right triangle as in the above problem, making the sides a right angles [illegible] of 3:4. What will be the length of the third side in terms of the same unit to which the [illegible] sides are known?

A Mechanical Co[illegible] Th[illegible] High School.

INSTRUCTIONS:- Problem 6--Part I.

1st. Draw [illegible] of the problem and read carefully its requirements.

2nd. To bisect angle A, first number the center of the circle C, the left end of the horizontal diameter 1 and the upper end of the vertical diameter 2. With 1 as a center and a radius greater than one-half of 1-2, draw an arc and with 2 as a center and the same radius, draw a second arc, intersecting the first. Draw C-3. This is the required bisector of angle A.

3rd. To trisect angle A, number the right end of the horizontal diameter 3 and draw 3 as a center and C as radius 3-4, drawing an arc cutting the circumference at 4. With 2 as a center and the same radius, draw an arc cutting the circumference at 5. Draw 5-C. Then draw from point 4 to C and 5 to C the required trisectors of angle A.

4th. To divide angle C from 3 equal parts, first divide it into two equal parts, as in (c), and bisect one of these parts, as in (c).

5th. To divide angle D into 3 equal parts, apply [illegible] (2) [illegible]

QUESTIONS:- I-

Can an acute [illegible] by the method employed [illegible]? Why not?

A Mechanical Co[illegible] For High Schools.

II-

How may such [illegible]

INSTRUCTIONS:- Problem 1--Part II.

1st. Draw the horizontal and vertical diameters of the base circle, marking the upper end of the vertical diameter C.

2nd. Lay off from C, upon the circumference of the circle, a distance equal to the radius of the circle by any two successive bisections as C-1, 1-2, 2-3. Through this point, 3, draw a line parallel to the base. From 1, lay off the other of these radii, and through this point, 4, construct a line parallel to the base of the triangle. Proceed in this manner until the seventh point is obtained. If accurately done, point 7 will fall at C.

3rd. Draw the lines 1-7, 2-7, 3-7, 4-7, 5-7, 6-7. These form the projected elevation of the pyramid.

4th. Draw the lines 1-2, 2-3, 3-4, 4-5, 5-6, 6-7, and 7-C. These form the projected plan of the pyramid.

5th. As in [illegible] lay off from the circumference of the circle, [illegible] to the [illegible] by the [illegible] in part one. Letter these points (), [illegible] as in the preceding part of the problem, [illegible] off this distance, [illegible] in this figure, the points [illegible] accurately done, point (7) will fall at (7).

A Mechanical Construction of Regular Polygons.

6th. Draw the lines a-b, b-c, c-d, d-e, e-f, f-g, and g-a. These form the required square.

7th. Draw a-b, b-c, c-d, d-e, e-f, f-g, and g-a. These lines form the required octagon.

QUESTIONS:- I-

What other regular polygons might have been constructed, by the second method, in the problem, by the use of the angle 45° in the first?

II-

Which of the polygons so constructed above has the sides all equal to the radius of the circumscribing circle?

III-

What is the simplest way to construct a hexagon?

EXERCISES:- Problem 7.

1st. Draw the line a-b.

2nd. Bisect the line a-b by perpendicular.

3rd. With (a) as a centre and a-b as a radius, draw an arc (a-b).

4th. With (b) as a centre and the same radius, draw a second arc, intersecting that just drawn at point (c).

5th. Bisect the angle (a- -) and produce to meet (a-b) in a point (d) and draw d-c.

6th. Bisect the angle (b- -) and produce to meet (a-b) in a point (e) and draw e-c.

A Mechanical Construction [illegible]

ing circles, [illegible] (a-a) [illegible] (b-b), respectively.

Call:- While [illegible] [illegible] accurate, [illegible] [illegible], [illegible] [illegible], known [illegible] "Application [illegible]".

QUESTIONS:- I-

[illegible] [illegible] the [illegible] [illegible] 3,5,7, and [illegible]?

II-

Mention [illegible] the construction of polygons might be of practical value, first, in [illegible]? Second, in industrial arts?

III-

Does a polygon constructed by the following method agree with that constructed in the 5th step of Prob. V?

1st. Draw the indefinite [illegible] diameter of the circle, which is to be [illegible] circumscribing the [illegible].

2nd. Erect the [illegible] either [illegible].

3rd. Lay off [illegible] and with [illegible] the [illegible] the [illegible]

A Mechanical Course for High Schools.

tical diameter, b' b'' to be cut repetting the horizontal radius, a' b' produced, in the point V.

4th. Now the length of each side of the required pentagon will be exactly equal to the distance from V to either end of the vertical diameter, and it should only be by this and the method which is given upon the circumference to have determined the vertices of the pentagon.

Plate No. 2.

GENERAL INSTRUCTIONS:

1st. Divide plate 2 as was done in the case of Plate 1, and make the same three plates.

Problem 3.

CIVIL :-

A heptagon all like (a-b) and a vertical line (a-3), bisecting each of the (3 3/8"-3 1/8"=3/8"). The length of (a-b) is 1" and that of (a-3) is 7". Draw the lines (a-2), (a-1), (1-b) and (b-2), thus forming a shoulder.

REQUIRED:-

The construction of a solid, by the "Method of Revolution" and by the "Method by Motion", with (a-b) and (a-3) as guiding curves. Also the construction of an approximate ellipse, bisected by the elevation (a-3-b-3).

A Mechanical Course for High Schools.

INSTRUCTIONS:- Problem 1--Part B.

1st. Draw the figure of the problem.

2nd. With (c) as a center and radius (a-c), draw a circle.

3rd. With (c) as a center and radius (c-e), draw a circle.

4th. Extend a-b to intersect the circumference of the circle just drawn and bisect each quadrant, extending the dividing lines to intersect each circumference.

5th. At the point where each of these lines intersects the smaller circle, draw a horizontal line to the right, perpendicular to meet it from the point at which the same line intersects the larger circle. The points a, d, b, and e, together with the short horizontal lines just drawn, determine an ellipse by the "Method of Revolution".

6th. Draw this ellipse as accurately as possible by hand, in pencil, and finally, by means of the French curves, a pleasing ellipse is produced. Follow the rules given in Plate I. Now construct this in one quadrant only.

Note:- Any line of an ellipse of revolution will be explained in Course D.

A Mechanical Construction for Hyperbolic Sections.

INSTRUCTIONS:- Part I.--Part II.

1st. With (a) as centre and any radius (a-c) draw an arc intersecting (a-b) in (c).

2nd. Join (b-c) and produce it to (d). With (b) as centre and radius (b-d) draw an arc, which will cross the Hyperbolic axis (a) and the produced line (b-c) in (e).

NOTE:- The minor axis must first be produced to obtain this point.

3rd. With (c) as centre and radius (c-e) draw an arc, which will cut (a) in (f). With (b) as centre, and radius (b-f) draw an arc, intersecting the produced line (b-c) in (g).

4th. With (f-g) as radius and (f) as centre, draw an arc intersecting (a) in (h). Produced (f-h) to (i).

5th. Draw the lines (g-i),(i-f), (g-f) and (h-f) to form a right angled triangle.

6th. With (g-a) as radius and (g) as centre, draw an arc cutting (g-i) in (k). Produce (g-k) to (j), and with (g-a), (l).

7th. With (i) as centre and radius (i-l) draw an arc, cutting the line of Hyperbolic with (i-h) produced in (m), and with (i-j) produced in (n).

A Modern Moral Courage For High Schools.

6th. With centre (E) and radius (E-H) draw an arc. If the construction has been correctly carried out, this arc will just touch (A) and meet the point (I).

9th. With (A) as centre and radius (A-J) draw another arc. This should pass through (C) and exactly meet the point (M).

10th. The curve (a-H-d-I-b-M-c-J-a) is the required Quadricentric ellipse. Ink this curve in red, so that the points of departure from the ellipse of revolution, which is exact, may be noted.

11th. Ink construction in, pale pink and only, so as not to confuse with Part I.

Miscellaneous:- Problem 8--Part III.

1st. From (A) drop a perpendicular upon (c-b), both ends of the base of the perpendicular (q) and its intersection with (c-d), (3).

2nd. In the same way drop a perpendicular from (A) upon (d-c), both ends of the base (m) and its intersection with (c-b), (4).

3rd. From (3) drop perpendiculars upon (c-c) and (c-d), both ends of which base (r) and (s), respectively. In precisely the same manner, drop perpendiculars from (4) upon (c-b) and (c-d), both ends of which base will pass through points (c) and (c).

4th. With (A) as centre and radius (A-m) draw an arc from (m) to (_).

A Mechanical [illegible] Circle.

5th. With (b) as [illegible] radius (b-r), draw an arc [illegible] (r) to (q).

6th. With (a) as [illegible], [illegible] intersecting (p) and (n).

7th. With (n) as [illegible], draw an arc intersecting (r) and (q).

8th. The arc, just described, will [illegible] ellipse in the [illegible] points (r, q, p, n), and these points are the [illegible] of tangency.

QUESTION :- I-

What geometric figure [illegible] by the plane surface passing [illegible] the plane of the observer's vision?

II-

How may an ellipse [illegible] by means of two pins connected by a cord?

III-

What practical application [illegible] ellipse can you mention, first [illegible] mechanical [illegible] tion? Second, in the [illegible] art?

Problem 9.

CIVIL :-

A hexagon [illegible] in a [illegible] radius. The centre (o) is [illegible] 2/4"].

A Mechanical Drawing Problem. High School.

REQUIRED:-

The transfer of the figure by means of coordinates, so that point (A) will fall at A; the transfer of the figure by means of angles, or polar co-ords, that, so that (B) will fall at B and finally, the transfer of the figure by means of parallels, so that (C) will fall at D.

Check:- Locate a point (X) in each of the above cases. With (X) as a center and a radius (o-a), draw a circle. This should pass through the transferred positions of (a-a-a-a-a).

ENGINEERING:- Problem No.6--Part I.

1st. Draw what is given of the problem in Fig. 2, Plate 6.

2nd. Locate a point A (3 1/2"R-14 1/2"D), B (2 3/8"R-11 1/2"D) and C (3 1/2"R-17"D).

3rd. Draw any line x-y (see Fig 2, Plate 6) and construct perpendiculars to it at each of the points (a,b,c,d,e,f,g).

4th. Number the points of intersection, as indicated, 1 to 7.

5th. Through A draw line 1-1 parallel to (a-a) and lay off up to the point 1 on (1-1); with A', the transferred position of A, do the same with 1'.

6th. At 2' erect a perpendicular to (A-A') and locate 2 thereon; in like manner, 3', 4', 5', 6' and 7', which will occupy the same relative posi-

A Mechanical Course for High Schools.

tion to 2' that points 1 to 7 occupy with respect to point 1.

7th. At each of the points 1', 1' to 7', inclusive, erect a perpendicular of indefinite length.

8th. Upon the perpendicular at 1', lay off the length 1'-2'; upon 2'-3', lay off 3'-4', equal to 2-3; at 4', lay off 4'-5', equal to 4-5, and continue this method for the remaining points.

9th. The lines (1'-2'), (2'-3') etc. will form an inner hexagon, which is the hexagon in a circle by the method.

Illustration:- Problem No.6--Part I.

1st. From any point (A) on side the hexagon (see Fig. 2, Plate C), lay off a length of the diameter of the circle.

2nd. Draw a line through B, parallel to (b-a) and lay off upon it the length (B-a'), equal to (b-a).

3rd. To find a point of tangency with (a) and (a'), construct arcs of indefinite length.

4th. Through the point of intersection of the arcs drawn with (a) as center, and the line (a-1), 6; with (a-2), 5; and with (a-3), 10;------ with (a-6), 12. (See Fig., Plate C).

[illegible]

[illegible]

[illegible]

A Mech. Lab. Course For High School Use.

contact with (e-f), to [illegible] in D, [illegible] may be necessary to [illegible] Edit, select an edge that will [illegible] to be moved [illegible], and [illegible] treme care to [illegible] moved from [illegible] to the other [illegible] motion will be [illegible] ing through (2). [illegible] used.

Ex4. After the line through (2) has been drawn, [illegible] (e-f), as shown in [illegible] locate point (1) [illegible] to (e-f).

Ex5. Locate [illegible] (2), and (3) to locate [illegible] com pointing [illegible] ed hexagon [illegible]

Check: [illegible] once by [illegible] the other [illegible] (e-f). [illegible] to [illegible]

Quiz Time:

1-

[illegible] for the [illegible]

2-

[illegible] on a "Hi Lo", [illegible] would you [illegible] should it be used?

A Mechanical Con[illegible] High School.

Problem 10.

GIVEN:-

A circle of 2 1/2" diam. Point (P) located 3 1/2"D-in 3/4"L.

REQUIRED:-

To construct 10 arcs of circles, tangent to each of the 4 sides of the square given, and to each other, which shall be of such radii that they are to be tangent to the circle and to two lines tangent to it, one of which shall be parallel to the given line AB, the other to form a tangent which shall be parallel to the given line CD, thus forming a tangent circle around the circle.

CONSTRUCTION: Problem 10,--Plate I.

1st. Draw AB parallel to CD, and 1" from it. Construct EF perpendicular to AB and CD, and 1" from it. Draw GH and JK parallel to EF and 1" from it.

2nd. Bisect the angles formed by the intersection of AB and CD, and the angles formed by the intersection of EF and GH, dividing the circle into 8 equal parts.

3rd. Extend the bisectors of the angles formed by the intersection of AB and CD, to intersect the circle at L, M, N and O. Bisect the angles formed by the intersection of these lines.

4th. Extend these lines to intersect the circle at P, Q, R and S. Connect the points of intersection of the circle and the lines AB, CD, EF and GH.

5th. With (o) the intersection of AB and CD, and (o-1) the intersection of AB and EF, describe the arc 1-2-3. With (o) and (o-2) describe the arc 4-5-6. With (o) and (o-3) describe the arc 7-8-9. With (o) and (o-4) describe the arc 10-11-12.

6th. With (o) and (o-5) describe the arc 13-14-15. With (o) and (o-6) describe the arc 16-17-18. With (o) and (o-7) describe the arc 19-20-21. With (o) and (o-8) describe the arc 22-23-24.

Mechanical Drawing Through Schools.

draw a circle, AB, of any size from (x), taking every point in the circumference of the circle with the dividing leads, (x). Whose will be all of which will be in all.

(iii). With a radius of any length, and with any point, as (x), as centre, draw the circumference of the circle, A B. Now divide the circle into any number of equal parts, as (x), from one of these points as a centre, and with the same radius, describe arcs which will cut the circumference in the points, A and B. Join A and B, and A and B, with straight lines. Then A B will be the side of a regular figure, which will be inscribed in the circle.

Problem:- This would be difficult to draw by any method of geometrical construction, but may be easily done by the method just described. The circle must be divided into as many equal parts as the required number of the regular figure.

Problem V:- Divide a line into any number of equal parts.

1st. Draw a line, A B, of any length, and from one of the ends, as A, draw a line, A C, at any angle.

2nd. Take any convenient length, and from A mark off, from A to C, as many of these lengths as the line is to be divided into, as A, B, C, D, E, F, and G, as shown in the figure.

3rd. Join the last point, G, to the end, B, of the line, A B, and through the other points, (6-7) and (5-7), draw lines parallel to G B, cutting A B in the points, F, E, D, C, and B, respectively.

4th. Draw a line, A B, of any length, and from one of the ends, as A, draw a line, A C, at any angle. Take any convenient length, and from A mark off, from A to C, as many of these lengths as the line is to be divided into, as A, B, C, D, E, F, and G, as shown in the figure.

5th. Join the last point, G, to the end, B, of the line, A B, and through the other points, (6-7) and (5-7), draw lines parallel to G B, cutting A B in the points, F, E, D, C, and B, respectively.

6th. Confirm that A B is divided into the required number of equal parts, as A, B, C, D, E, F, and G, by measuring each of the parts with the dividing leads, from A to B.

A Mechanical Course [illegible] High Schools.

QUESTIONS:- I-

Have the principles of this problem any practical application? Give examples.

II-

Can the following problem be solved graphically by this means? Required the diameter of each of 10 roller bearings to roll within a collar of 5" diameter, with 1/8" clearance between adjacent bearings. Give reasons for your answer.

Problem No.11

GIVEN:-

A circle of given radius, with center (c), located (12"D-17 1/2"R).

REQUIRED:-

The construction of four spirals arranged symmetrically with respect to the horizontal and vertical diameters of the given circle.

INSTRUCTIONS: Problem No.11--Part I.

1st. Draw the horizontal and vertical diameters of the given circle and extend them indefinitely.

2nd. Divide each quadrant into three equal sectors and starting with point 1, as the upper end of the vertical diameter, number the ends of the radii, just drawn, from 1 to 13 in a clockwise direction.

A Mechanical Construction of Epicycloid.

2nd. Draw [illegible] through
of the [illegible] by the [illegible] from the point -
ly in the [illegible]. (Note:- A [illegible]
the [illegible] of any
diameter).

3rd. Lay off [illegible], the
distance (1-2) [illegible] (1-2), and
respectively, [illegible]. Number the points
thus located, [illegible].

4th. Lay off [illegible] point
at 2, [illegible] (1-2) [illegible] the
point obtained (2'). [illegible] upon the tangent
upon the diagonal [illegible] and
number the point [illegible].

5th. Lay off [illegible] point 11,
in the [illegible], three
times the distance (1-2) and again number the point obtained (2'). Also lay off upon the tangent at point 5, in the same general direction as at 2, a distance equal to that just measured from 11. Number this point 12'.

7th. It will be [illegible],
point 1', [illegible] will form a curve, [illegible] and
that [illegible], [illegible] ( ) [illegible] point -
ing to point (1') and [illegible] shadow curve,
embracing [illegible]. Continue [illegible] until
a [illegible] curve, which [illegible], [illegible]
through 6'0 [illegible], [illegible] it
has [illegible] its full [illegible]. The two
points consecutive upon [illegible] will be
twelve with distance equal, i. e. 12' (1-2).

A Mechanical Con[illegible]ch.

Will:- To [illegible] in a [illegible], in a mechanical [illegible]ing [illegible] [illegible] out [illegible].

Sub. Recall [illegible] and [illegible] French curve.

Engineering:- [illegible].

Sub. [illegible] tangent [illegible] determine, (or) [illegible].

Sub. [illegible] each [illegible] tangent [illegible] i.e. [illegible] [illegible] and [illegible].

Sub. Complete [illegible].

Will:- [illegible] to [illegible] [illegible] [illegible] [illegible] mation, [illegible] [illegible] [illegible] [illegible]

A Mechanical C[illegible] Tip High Voltage.

III-

Has the spiral cut [illegible] a ... in mechanical contact with [illegible]?

III-

How may a spiral be [illegible] will not cut?

A Lesson from Cedric the Saxon.

Introductory.

Before entering upon the study of Plate 6, and the three Key Drawings, it will be necessary to learn a great deal of detail by the Double-piece of this book. In this lesson, the writer has chosen a typical example of the Double-pen-point in the hope that, by repeated reference to the lesson, repeated reference to the Double-pen-points will be unnecessary.

To hold the Double-pen-point, hold it as the Single-pen-point, but with the two points parallel.

I-

(Line Practice)

The first step in the Double-pen-technique is "Double-pen-line". It consists of two "Double-pen-lines", drawn so that the

[illegible]

[illegible]

A Mathematical Co[illegible] For High School [illegible].

[illegible] by the Instructor. The propositions [illegible] by "type" [illegible] [illegible] [illegible]

A Mechanical Method of Making Perspective Drawings.

since all of the lines of sight must appear to meet at points. This is because the eye of the observer is supposed to have shifted from position to position to be looking at right angles to every line of width, instead of supposed to look up all the vertical lines as in a plan view.

In the side view, or elevation, the height and depth appear in actual size, but in this case, the lines of length appear to meet at points.

The form of projection employed above is known as "orthographic" or "parallel" projection. A great deal of thought and careful study will be required before any satisfactory may be hoped for in this work. The student must understand that the various views of a set of "working drawings" are not such as would ever appear to the eye looking upon the object they represent. They are purely theoretical in this respect and although perfectly true of course at any

infinite distance from the object, so that the rays of light reflected from it come in parallels, or that the eye is supposed to occupy an infinite number of positions simultaneously, one position directly above every projected point of the object, as in the case of the T-square experiment for a single point.

III.

(Arranging the Views)

Since any two views have one dimension in common, i.e. the plan and elevation views have width; the elevation and side views have height; and the plan and side views have length; they can be so placed that this common dimension may be readily projected, by vertical or horizontal projection lines, from one view to another.

Notice, in the typical case, that considering elevation, which is the front view, as the base point, vertical lines below the plan; and to the left and right are used to project points in the

same horizontal lines, and that the corresponding points of the plan and side views are projected in such a manner as to hold the points of width in the same relative position at all times.

IV-
(Axes of Projection)

The views will be seen to be separated by a horizontal and a vertical line which are known as the "axes of projection". The theory of their derivation, together with a much more extended and comprehensive discussion of projection, will be found in Course D2 and the courses succeeding it, but for the present, these lines will be regarded simply as the boundaries of the various views to which the projecting lines are either perpendicular or parallel.

Let a small scale drawing, showing the most important lines of each of the views, be made at this time upon a sheet of practice paper.

Cut from this the quadrant containing the circular arcs and fold along the axes of projection. The plan, front, and side views will occupy planes that are perpendicular to each other, the plan view being horizontal and the front and profile views vertical in position. It should now be clear to the student that each of the views represents a perpendicular projection from an imaginary object, which is supposedly standing back of the vertical planes and below the horizontal.

Y-
(Broken or Dotted Lines)

It should next be noted that certain lines, not visible because of intervening surfaces, must be shown. These lines are drawn "dotted" or "broken". (See Plate 2, line C) Care should be exercised in the use of these lines, for attempting to indicate the position of all sch-

[illegible]

ocalled pa[illegible]e, so many [illegible] [illegible] [illegible] [illegible] [illegible] [illegible] [illegible] [illegible] [illegible] a meaningless [illegible] [illegible] [illegible] [illegible] [illegible] [illegible] [illegible] [illegible] [illegible]

make some point clearer to those who will later have the task of making the finished article from given designs.

The dotted lines in the second figure serve to indicate a possible position that a movable part may occupy as, for instance, the middle lead in this problem. In the front view, it will be noted that the lead is to the left as shown; but that its position, when up, is indicated by dotted lines to the right and to the left. At the right, the lead is raised, but the position shown is indicated in the same manner.

VI.

(Sectional Drawing.)

Every person who has had much to do capable of explaining what is meant by the "sectional elevation". To understand the theory of its construction, it is only necessary to think of one portion of the object as cut away,

[illegible]

leaving [illegible] one-half [illegible] areas.

Again, [illegible] plane, [illegible] the [illegible] lower right-hand [illegible] plane, [illegible] considered [illegible], as a whole, [illegible] and [illegible] areas [illegible] the [illegible], [illegible] taken [illegible] for [illegible].

(Use [illegible] Watch-Fob.)

It [illegible] any [illegible] [illegible] by a plane, [illegible] this [illegible] drawn across [illegible].

A Mechanical Course For High Schools.

"cross-hatching or outline-lining". In case the project is an instrument entirely of curvilinear, such as a, for example, turn the various pieces are either drawn entirely by working the right and left curves, adjusted pieces. Where differ in a blank, such as door, lunet, rubber, etc. use tool to the same problem, different "sets" and duplicate is difficult these entirely, i.e. the curve from the brace is a piece of right radius, used entirely; for a right line, a light and heavy line, used alike; for, a series of very heavy lines, drawn closely, etc.

Inquiry will, finally, be made as to the reason for making the brace-wire in which, if not clear upon the second line and by, for example, a little entire length by the several places we can

[illegible]

[illegible]

[illegible]

[illegible]

[illegible]

[illegible]

[illegible]

[illegible] time at first and it will not be long until you are making excellent figures as rapidly as you formerly made those that were illegible.

[illegible]

[illegible]

[illegible]

A Mechanical Device For High Definition.

[illegible]

Referring [illegible].

[illegible] [illegible] [illegible] [

A Revolutionary Scene in Virginia.

[illegible]

[illegible]

[illegible]

A Mechanical Course for High Schools.

themselves differ by multiples of 1/8", 1 1/8", 1", and 1" should be made to order only when required. The choosing of the proper size of a drill is a small matter, but by the proper use of the drill gauge it can be done in the shortest time necessary.

DRILLS.- Before drilling any hole of any of the sizes, No. 1 to No. 60, inclusive, study the table of drills and their numbers, as shown by the letter and number on the possible number of drills.

QUESTIONS:-

To accurately measure the diameter of any article, will enough drill No. 1 to No. 60 inclusive, and Letter A, Letter Z, and the different answers to the following questions:

I-

How are drills numbered and lettered?

Sharp Steel

A Mechanical Comparison of Light Schools.

II-

How can the area of light for [illegible] efficiency be determined by a [illegible] of Foot-candles?

III-

What [illegible] of [illegible] [illegible]?

IV-

How can you [illegible] [illegible] equipment?

V-

What [illegible] [illegible] [illegible] equipped [illegible] [illegible]?

VI-

What [illegible] [illegible] [illegible]

Prob 12. BOOK BLOCKS.



Isometric Sketch.

GIVEN. An isometric sketch of book blocks or of optional problem number one.

REQUIRED.

The making of free-hand sketch of isometric here shown; also the making of working drawings in plan, front view, and side view, these to be dimensioned to conform to proportions of sketch.

INSTRUCTIONS.

Place the point of intersection of the horizontal and vertical axes of projection [See Foot Note]

QUESTIONS.

Which lines of the sketch will be foreshortened in the plan view? Which in the front view? Which in the side view?

What relative position must a line and a plane occupy in order that the projection of the line upon the plane be equal to the line?

Prob. 13. SMALL TOOL CHEST.



Isometric Sketch

GIVEN. Isometric sketch of tool chest.

REQUIRED.

Same as in preceding problem.

INSTRUCTIONS.

Place the point of intersection of the horizontal and vertical axes [See Foot Note]

QUESTIONS.

How many times as large is 1in., to a scale of 4in per foot, as it is to a scale of $\frac{1}{4}$in per foot?

What is meant by the term DETAIL? Is it more convenient to show detail in large or small scale drawings?

What is meant by an ISOMETRIC DRAWING? Why is it that isometric drawings always seem more or less distorted?

Prob 14. FERN BOX.



Isometric Sketch.

GIVEN. Isometric Sketch of a fern box.

REQUIRED.

Same requirements as in preceding problems.

INSTRUCTIONS.

Place the point of intersection of the horizontal and vertical axes [See Foot Note]

QUESTIONS.

What other types of joint could be used in place of the dovetail in this and the preceding problem?

Why is zinc a satisfactory metal to use in places where water is to be retained? What other metals also resist corrosion and, for this reason, are largely used in the building trades?

Prob 15. TABOURETTE.



Isometric Sketch

GIVEN. Isometric Sketch of tabourette or of optional problem number two.

REQUIRED.

The same as in all other problems of this plate. It is also required that the pupil at the completion of the problems make a complete bill of material for each exercise.

INSTRUCTIONS

Place the point of intersection of the vertical and horizontal axes [See Foot Note]

QUESTIONS.

What are the characteristics of the mission and craftsman styles of furniture and architectural design?

NOTE. PLATE No.6 IS TO CONSIST OF TWO PROBLEMS; THE FIRST TO BE A CHOICE OF PROB. 12 OR 13 AND THE SECOND EITHER PROB. 14 OR 15. WHEN THE PUPIL HAS DECIDED UPON HIS PROBLEMS, THE INSTRUCTOR WILL SUPPLY OMITTED INSTRUCTION DATA.

A MECHANICAL COURSE FOR HIGH SCHOOLS. BY ROBERT A PERKINS.

PLATE H.	MECHANICAL DRAWING COURSE D.1	DRAWN BY R.A.Perkins

A Mathematical Question from Night Scene [illegible].

[illegible] ? What [illegible] ? What [illegible] ?

VIII-

Having [illegible] a [illegible] [illegible] [illegible] view, how [illegible] [illegible] [illegible] [illegible] [illegible], [illegible] [illegible] [illegible] [illegible]

A Lucchese feast [illegible]

[illegible] [illegible], [illegible] [illegible] [illegible]

[illegible]

Problem 17.

In this problem [illegible]
[illegible]. As in Prob. [illegible], [illegible]
[illegible], [illegible], [illegible]
[illegible] [illegible]
[illegible] [illegible].

In this [illegible], [illegible]
[illegible] [illegible]
[illegible] [illegible]
[illegible] [illegible].

[illegible]

Problem 18.

[illegible] [illegible] [illegible]
[illegible] [illegible] [illegible]
[illegible] [illegible].

In this [illegible], [illegible]
[illegible] [illegible] [illegible]
[illegible] [illegible] [illegible]
[illegible] [illegible] [illegible].

[illegible] Course [illegible] Drill.

Problem 17.

In making this [illegible] necessary for the [illegible] to proceed as follows:

1st. Draw a plumb, and the [illegible] line, in the plane, [illegible], respectively, to the [illegible] and [illegible] of projection.

2nd. Out [illegible] the [illegible], as [illegible] the [illegible].

3rd. After [illegible] this plane construction, [illegible], using this [illegible] the [illegible] of the [illegible].

4th. Return to the plane [illegible], after the [illegible], and [illegible] projection.

Note: See [illegible] Problem No. 11, Page.....

Prob.16. DRAWING TABLE.

GIVEN.

The isometric of a drawing table.

REQUIRED.

The drawing of the sketch and the dimensioning of same, also the making of working drawings in plan, front, and side views. It is further required that the principle parts be detailed and dimensioned.

INSTRUCTIONS.

Place the point of intersection of the axes of projection [See Foot Note]

QUESTIONS AND SUGGESTIONS FOR SUPPLEMENTARY STUDY.

What are jigs?

What are templets?

Explain in a short report, illustrated with freehand sketches, how a set of templets and jigs could be made to aid in the rapid construction of a set of tables like the above isometric. Would it pay to construct a set of jigs to build one or two tables only?

Does lumber show the greatest shrinkage and expansion, due to a variation in the amount of moisture in the wood, in the direction of the grain or across it? On this account what devices are made use of in attaching table tops, like the above, to the transverse supports?

Make complete bill of material required for above drafting table, and also specify the most satisfactory wood and finish for each of the parts. What would be the cost of this material figured at local prices?



Isometric Sketch.

Prob 17. FOLDING SCREEN.

GIVEN.

The isometric of folding screen or of serving table shown in optional sketch number three

REQUIRED

A free-hand drawing of the problem and the making of working drawings for same in plan, front, and side views. It is also required that, at the completion of the plate, a complete bill of materials be made. Detail completely.

INSTRUCTIONS.

Place the point of intersection of the axes – [See Foot Note.] If the screen is chosen by the student, let the middle section be placed parallel to the vertical plane of projection, the other two sections being inclined 30° right and left respectively. [See Plan View below]

QUESTIONS FOR SUPPLEMENTARY STUDY.

What are acid stains, water stains, and oil stains? What advantages has each?

What are paste fillers and liquid fillers? Why are they used?

What is varnish? Shellac? Wax? How and why is each used?

What inexpensive woods, by the use of stains, may be quite satisfactorily substituted for mahogany, Circassian walnut, etc.?



Isometric Sketch.



PLAN VIEW.

NOTE. PLATE No.7 IS TO CONSIST OF ONE PROBLEM; PROB.16, PROB.17, OR OPTIONAL PROB.3. WHEN THE PUPIL HAS DECIDED UPON HIS PROBLEM, THE DATA OMITTED FROM "INSTRUCTIONS" WILL BE SUPPLIED BY THE INSTRUCTOR.

A MECHANICAL COURSE FOR HIGH SCHOOLS. BY ROBERT A. PERKINS		
PLATE I	MECHNICAL DRAWING. COURSE D.1.	DRAWN BY R.A.Perkins

[illegible]

Block No. 7.

[illegible]
[illegible] Block No. 7, Section 21.
[illegible]
[illegible]
[illegible]

[illegible]
[illegible]
[illegible]

Block No. [illegible].

[illegible]
[illegible]
[illegible]

Prob. 18.

Desk With Light.



Isometric.

Given:-Isometric drawing of desk or of optional problem number four.

Req:-Working drawings in plan, front, and side views; also complete details.

Instructions:-Place the point of intersection of the horizontal and vertical axes [See Foot Note]

Questions:-What is meant by the following terms: Quarter-sawed, flat-sawed, and edge-grained? Which of these may be produced only by considerable waste of material? Which method of production will insure the highest market price?

What would be the cost of desk if made of flat-sawed red oak? Quarter-sawed white oak? Flat-sawed white oak?

Prob. 19.

Table Lamp for Hall.

Given:-Isometric of hall lamp or of optional problem number six.

Req:- The drawing of sketch of the problem chosen, also the making of working drawings in plan, front, and side views, and complete details. Make bill of material and figure cost of same.

Instructions:- Place the point of intersection of the axes of projection [See Foot Note]



Isometric.

Note. The solution of Prob. 18, Prob. 19, Optional Prob. IV, or Optional Prob. VI will constitute the work of this plate. When the problem has been selected, the teacher will supply the missing data in "Instructions."

A Mechanical Course for High Schools. By Robert A. Perkins.

Plate J. | Mechanical Drawing. Course D1. | Drawn By R.A. Perkins

Prob. 20.

COMBINATION CHAIR AND TABLE.



Isometric Sketch of card table with arm pockets closed.



Isometric Sketch of chair with one of the arm pockets open.

GIVEN:- Isometric drawings of convertable table and chair.

REQ:- The making of working drawings of the above problem in plan, front, and side views, transverse section and details.

INSTRUCTIONS:- Place the points of intersection of the axes of projection, A and B of the figure, 8½"D-8"R and 8½"D-16"R respectively. Ar-



range Plate No.9 as indicated above.

The shop sketch of this problem will be included on plate with bill of material and estimate of cost.

A MECHANICAL COURSE FOR HIGH SCHOOLS
BY ROBERT A. PERKINS.

PLATE K	MECHANICAL DRAWING COURSE D1	DRAWN BY R.A.P

[illegible].

[illegible].

[illegible]

[illegible]

[illegible]

III.

SERVING TABLE.
MAY BE SUBSTITUTED
FOR REGULAR
PROB. 17



I.

DRAWING-BOARD WITH DRAWER.
FOR USE UPON COMMON TABLE FOR HOME WORK
MAY BE SUBSTITUTED FOR REGULAR PROBLEM NO. 12



V & VI

HALL CLOCK

MAY BE SUBSTITUTED FOR
PROB 16 OR PROB. 19.



II.

DRAFTSMAN'S STOOL.
MAY BE SUBSTITUTED FOR REGULAR
PROB. NO. 15





IV.

BENCH

MAY BE SUBSTI-
TUTED FOR REGULAR
PROB. No. 18

A MECHANICAL COURSE FOR HIGH SCHOOLS.
BY ROBERT A. PERKINS.

PLATE	OPTIONAL PROBLEMS	DRAWN BY
L	COURSE D1	R.A. Perkins

[illegible]

[illegible]

[illegible]

BOOK III.

Table IV

Table V

VASES

THESE MAY BE USED AS THE LAST EXERCISE OF S3 AND FOR PLATE 2 D2 WHERE SUBSTITUTE PROBLEMS ARE DESIRED.

A MECHANICAL COURSE FOR HIGH SCHOOLS.
BY
ROBERT A PERKINS
FRONTIS-PIECE MECHANICAL DRAWING
COURSE D2.



[illegible]

[illegible]

[illegible]



A MECHANICAL COURSE FOR HIGH SCHOOLS.
BY ROBERT A. PERKINS.

PLATE A.	MECHANICAL DRAWING COURSE D2.	DRAWN BY R.A.Perkins

[illegible]

[illegible]

IV-

[illegible]

A MECHANICAL COURSE FOR HIGH SCHOOLS.
By Robert A. Perkins.

PLATE B

Mechanical Drawing. Course D 2

DRAWN BY R A Perkins





AUXILIARY VIEW.

MAY BE TAKEN AT ANY ANGLE TO HORIZONTAL OR VERTICAL PLANE.

A MECHANICAL COURSE FOR HIGH SCHOOLS
BY ROBERT A. PERKINS.

PLATE	MECHANICAL DRAWING	DRAWN
C	COURSE D2.	BY R.A. Perkins

[illegible]

[illegible]

[illegible]

A MECHANICAL COURSE FOR HIGH SCHOOLS
By Robert A Perkins.

PLATE D	MECHANICAL DRAWING COURSE D2	DRAWN BY R A Perkins



PLAN VIEW.



FRONT VIEW.



SIDE VIEW.

H. O. A. V.

[illegible]



FIGURE 1.



FIG. 2.

ILLUMINATION

See text for explanation of this plate.

A MECHANICAL COURSE FOR HIGH SCHOOLS. BY ROBERT A. PERKINS.		
PLATE F	MECHANICAL DRAWING. COURSE D2.	DRAWN BY R.A. Perkins



NOTE: Oblique auxiliary views find their principal use in showing the true relation existing between lines in planes which are inclined to the horizontal, vertical, and side-vertical.

A MECHANICAL COURSE FOR HIGH SCHOOLS.
BY ROBERT A PERKINS.

PLATE	MECHANICAL DRAWING	DRAWN BY
E	COURSE D2.	R.A Perkins





OPTIONAL · TURNING · EXERCISES.

MAY · BE · SUBSTITUTED · SINGLY, OR · AS · A · GROUP, FOR · THOSE · CORRESPONDING · IN · PL. G.

INDIAN CLUBS.



DUMB-BELLS.

CROQUET BALL.



CROQUET MALLETS.

STAKE.



PLAN.



SECTIONAL ELEVATION
PULLEY.

NOTE:

For requirements, instructions, etc. for plate one course D2 see text.

A MECHANICAL COURSE FOR HIGH SCHOOLS. By Robert A. Perkins.		
PLATE ·G·	MECHANICAL DRAWING. COURSE D2.	DRAWN BY R.A. Perkins
SHADING·EXERCISE.		



FIG.1
PILOT WHEEL.

FIG.2
BALANCE WHEEL

FIG.3
HAND WHEEL

NOTE: Plate two, of this course, will consist of plan, elevations, sections, and details of one of the above wheels rendered in flat washes. The wheel designed will be constructed as last exercise of Course S3.

A MECHANICAL COURSE FOR HIGH SCHOOLS.
BY ROBERT A. PERKINS.

PLATE	MECHANICAL DRAWING · COURSE D2 ·	DRAWN BY
H		R.A. Perkins

A MECHANICAL COURSE FOR HIGH SCHOOLS.
BY ROBERT A. PERKINS.

PLATE	MECHANICAL DRAWING	DRAWN
I	COURSE D2	BY R.A.Perkins



FIG. 1



FIG. 2

CABINET DESIGN.

Suggestions, for the student, that may prove helpful in the working out of plate three, course D2. See text for further information.



A MECHANICAL COURSE FOR HIGH SCHOOLS.
By
ROBERT A PERKINS.

MECHANICAL DRAWING
COURSE D2
PLATE J









A Mech[illegible] [illegible] [illegible] [

A Mechanism [illegible]

Prob 1

Given:- Pt 0, 5¾ R - 3¼ D.
Pt a, 3½ - 3½ ÷ ¾
Pt b, 2½ - ¾ ÷ 3.

Required:- The true length of a b in plan, front, and side views. a and b will each be taken as the center of revolution, thus obtaining the true length twice in each view.

Note:- In this and all succeeding plates the co-ordinates of points will be given as follows; 1st distance from left border line, 2nd vertical projection, and 3rd horizontal projection. The + sign will always indicate locations above HO and the - sign points below HO

Prob.2.

Given:- Pt 0, 5½ R - 12¾ D.
Pt a, 5 - ¾ ÷ ¾
Pt b, 2½ - 3 ÷ 3½
Pt c, 1 - 1½ ÷ 2.
Pt d, ½ from c on bc
Pt e, 1" from b on ab
Pt f, 1" from a on ac

Required:- The drawing of triangles a-b-c and d-e-f in plan, front, and side views and the construction of development of the figure.

Note - The explanation given below is for the development of figures whose surfaces are triangles or some geometrical unit capable of subdivision into triangles.



Prob 3

Given:- Pt 0, 12¼ R - 3¼ D.
Pt 1, 13½ - ? ÷ 5/8
Pt 2, 15½ - ? ÷ 5/8
Pt 3, ? - ½ ÷ ?
The plan view of figure is a perfect pentagon the front view being a line inclined 45° to HO.

Required - The construction of the side view of figure and also the determining of true area of same, in the plan view, by revolving entire figure into plane parallel to H. Check results with true lengths obtained by use of V and SV projections.

Prob 4.

Given:- Pt 0, 17½ R - 12½ D
Pt a, 14½ - 2 ÷ 1½
The plan view a circle with center at o and side view a line at 45° to AO

Required - Front view and development of figure.

Note - Draw horizontal and vertical diameters and subdivide quadrants into three equal parts. Number points as indicated. Find true length of lines 3-5, 2-6, 1-7, 12-8, and 11-9, also determine perpendicular distances 4 to 3-5, 3-5 to 2-6 etc. These dimensions are coordinates of required true curve.

To develop any geometrical figure, such as is shown in Prob 3, a convenient way to proceed is as follows; draw 2-5 and 3-5 and determine their true lengths as well as those of 1-2, 2-5, etc. Lay off true length of 1-2, as indicated in figure below, and then with points 1 and 2 as centers and with true lengths 2-5 and 1-5 as radii draw arcs intersecting at 5. Now with points 2 and 5 as centers and with true lengths 2-3 and 5-3 as radii draw arcs intersecting at 3. Finally, to determine the location of point 4, take points 3 and 5 as centers and with radii 3-4 and 5-4 draw arcs intersecting at 4. The results obtained by this method should agree exactly with those obtained in any other manner. The student should verify the above statement by checking his results in Prob.3 in this way.

DEVELOPMENT OF PROB 3



NOTE:-

Neat and accurate solution of the four problems stated above constitutes the work required in PLATE 4.

See text for instructions, questions, etc

A MECHANICAL-COURSE FOR HIGH SCHOOLS.
BY ROBERT A PERKINS.

PLATE K | MECHANICAL DRAWING · COURSE D2 · | DRAWN BY R.A Perkins

A Bibliography of Books and Articles Cited in Text.

Bell, [illegible], [illegible] from the [illegible], [illegible], [illegible],



FIGURE 1.

PLANES.



FIGURE 2

NOTE:— For information, instructions, questions, etc. pertaining to this plate see accompanying text.

A MECHANICAL COURSE FOR HIGH SCHOOLS. By ROBERT A. PERKINS.		
PLATE L	MECHANICAL DRAWING COURSE D2.	DRAWN BY: R.A. Perkins

Problem 1.

GIVEN:– An oblique pyramid with vertex o, $3\frac{3}{4}-\frac{1}{2}+1\frac{3}{8}$, and with base inclined 30° to H and perpendicular to V as indicated. Pt. 1, $1\frac{5}{8}-6+2$, pt. 2, $4\frac{1}{2}-?+4$, pt. 3, $4\frac{1}{2}-?+1\frac{1}{4}$, and pt. 4, $3\frac{3}{8}-?+\frac{1}{2}$, determine lines of the base. The plane B is passed perpendicular to V and parallel to the base, $\frac{1}{2}$" above same, and plane A is passed perpendicular to V and parallel to H cutting O-3 at the same point as B.

REQUIRED:– The plan, front, and side views and development; the trace of both cutting planes to be shown in all views.



Problem 2.

GIVEN:– The plan and front views of a sheet-metal hopper. The plane 1-3-5-7 is perpendicular to V and inclined 30° to H as indicated. The points necessary to fully determine the figure are pt. 1, $13\frac{1}{4}-\frac{1}{8}+\frac{1}{8}$, pt. 2, $13\frac{3}{4}-3\frac{3}{4}+1$, pt. 3, $13\frac{1}{4}-\frac{1}{8}+4$, and pt. 4, $13\frac{3}{4}-3\frac{3}{4}+2$. In the plan view the hopper and throat appear as squares. The planes 2-4-6-8 and 2-4-6-8 are parallel to H and ½" apart. The vertical distance from 1-3-5-7 to the plane of 1-3-5-7 is 3¾".

REQUIRED:– The plan, front, and side views and development of the figure.



FIG. 1

NOTE

Either the elbow correction, shown in Fig.1, or the ventilator, shown in Fig.2, may be substituted for the hopper in Prob.2; the dimensions, location etc being determined by the pupil.



FIG. 2

NOTE.

Plate number 5 of course D2 will consist of the correct solution of Probs 1 and 2, or optional Prob 2, as noted. See Text.

A MECHANICAL COURSE FOR HIGH SCHOOLS
By Robert A. Perkins.

PLATE M	MECHANICAL DRAWING COURSE D2.	DRAWN BY R.A.Perkins



Problem 1.

GIVEN:-Two right pentagonal prisms of 3" altitude, the bases being inscribed in circles of 2" radius. The axis $X\text{-}\underline{X}$ is perpendicular to V and $Y\text{-}\underline{Y}$ to SV, point X being located $3-1\frac{3}{8}+1\frac{1}{2}$ and point Y, $4\frac{1}{2}-1\frac{1}{2}+3$. The lower face of each prism is to be placed parallel to H.

REQUIRED:- The plan, front, and side views of prisms and development of same showing complete line of penetration. Again lay out developments, after the completion of the plate, upon Bristol board or other heavy paper. Cut and fold these so as to check the accuracy of the drawing.

Prob.1



Prob. 2



Problem 2.

GIVEN:- Front and side views of a residence with gambrel main and dormer roofs and with a gable roof over the rear portion. The various angles of the roof and the dimensions of the residence are shown upon the elevations. Drawings are to be made to a scale of $\frac{1}{8}"=1'-0"$. Point a is located at $14\frac{5}{8}-\frac{7}{8}+\frac{3}{8}$.

REQUIRED:- The making of drawings showing plan, front, and side views with all valley lines accurately located. Make also a development of each of the roofs in the space below the elevations. As in the previous problem, check results by cutting out, folding, and fitting the various parts of the complete roof development.

Front View.

NOTE

If the student has time, the surfaces should be shaded with flat washes, as here shown, as the appearance of the plate is greatly added to by so doing

Side View.

NOTE.

Plate 6 of course D2 will consist of the accurate solution of the above two problems. See text for instructions, questions, etc.

A MECHANICAL COURSE FOR HIGH SCHOOLS. By ROBERT A. PERKINS.		
PLATE N	MECHANICAL DRAWING · COURSE D2 ·	DRAWN BY RAPerkins

Part 1.



O(4"D·5¾"R)



Part 2



O(4"D·17½"R)



Part 3.



O(13¾"D·5¾R)



Part 4.

NOTE:— THE CORRECT SOLUTION OF THE FOUR PARTS OF THE ABOVE PROBLEM WILL CONSTITUTE THE REQUIRED WORK OF PLATE SEVEN COURSE D2. FOR THE DATA, COMPLETE INSTRUCTIONS, QUESTIONS, ETC. FOR THIS PLATE SEE ACCOMPANYING TEXT.

A MECHANICAL COURSE FOR HIGH SCHOOLS
BY ROBERT A. PERKINS.

PLATE	MECHANICAL DRAWING	DRAWN
0	COURSE D2	BY RAPerkins



NOTE:— PLATE · NUMBER · EIGHT · OF · COURSE · D2 · WILL · CONSIST · OF · THE · WORKING · OUT · OF · THE · FOUR · PROBLEMS · IN · CONIC · SECTIONS · ABOVE · OUTLINED. FOR · DATA; INSTRUCTIONS; QUESTIONS; ETC. · SEE · TEXT · ACCOMPANYING. · SHADE · IF · TIME · PERMITS.

A MECHANICAL COURSE FOR HIGH SCHOOLS
By Robert A Perrin.

PLATE	MECHANICAL DRAWING · COURSE D2 ·	DRAWN BY
P		R.A.P.



FIG. 1.

FIG. 2







NOTE:- The making of working drawings of apparatus shown in Fig 1 will constitute the requirements of Plate 9, course D2. See text for complete instructions.

A MECHANICAL COURSE FOR HIGH SCHOOLS By ROBERT A PERKINS		
PLATE Q	MECHANICAL DRAWING · COURSE D2 ·	DRAWN BY R.A.Perkins



A [illegible] BOOKLET [illegible] Bs.

BOOK IV.

TABLE OF CONTENTS OF BOOK IV.

COURSE S1.

	Page.
Introductory Remarks.....	1 - 7
Instructions for Exercise No. 1, Plate A.	8 - 9
" " " No. 1, " B.	9 -16
" " " No. 2, " C.	16 -22
" " " No. 3, " D.	22 -29
" " " No. 3, " E.	29 -35
" " " No. 3, " F.	35 -39
" " Optional Exercise No. 1, Plate G.....	39 -47
Instructions for Optional Exercise No. 2, Plate H.....	47 -53
Instructions for Optional Exercise No. 3, Plate I.....	53- 56

LIST OF ILLUSTRATIONS
of
COURSE S1.

	Page.
Frontis Piece, Book Block Details.....	1
Tool Box Details.....	10
Farm Box Details.....	17
Tabourette Details.....	24
Drafting Table Details.....	26
Screen Details.....	36
Drafting Board and Drawer Details.....	41
Drafting Stool Details.....	48
Serving Table Details.....	50



Fig. 1.

Explanation · of · Drawing.

A and E :— Veneer of front and back face. Original design to be cut from front face before gluing.

B and D :— Soft wood sections with vertical grain.

C :— Soft wood section with horizontal grain.

F and G :— Veneer of sides May be left plain, as here indicated, or contain a panel or design, as suggested in the shop sketch of Prob. 12, D1.

H and I :— Top veneer

J, K, and L :— Front and side pieces of base. Made of the same hard wood as veneer.

Note :— For shop instructions see accompanying text.



Fig. 2.

Book Block Construction Designed in Prob. 12, Course D1.

Note :— The exact dimensions and design will be taken from the student's Plate 6, Course D1. The face will be designed with as much originality as possible, the ideas suggested in this plate and in Plate H, D1 showing about what is required.

A Mechanical Course for High Schools. By Robert A. Perkins.		
Plate A.	Wood · Working. · Course S1 ·	Drawn By R.A.P. & L.M.S.

A Mechanical Course For High Schools.

WOOD WORKING.

Course S1.

As previously explained, not less than one hundred and eight hours of shop work are required in the seventh and eighth grades as a prerequisite to the course here presented; this time to have been spent in a carefully supervised study of the construction, care and method of using the more important wood working tools; in learning to distinguish the characteristics of various woods; and in exercises in joinery requiring the use of both mechanical and glued joints. Without arranging for the above preliminary instruction, this course should not be attempted.

Assuming then that the student has received the necessary training in the foregoing important introductory details, we will proceed at once to an explanation of the problems of

the course. These explanations will be given in the same order as the working drawings appear in Course D1, the pupil selecting from them the three that he designed for his course in Shop S1.

Plate A- Course S1.

In Plate A of Course S1 will be found the details for the construction of the Book Block designed in D1, Prob. 12. The following outline will be found helpful in its construction.

First:-

Construct the parts B,C, and D of clear white pine or white wood, remembering that the grain of B and D is to run vertically and that of C horizontally. Why?

(a) To find the dimensions of the pieces, substitute in the following equations.

Let T equal thickness of block taken from design of Prob. 12,
t equal thickness of veneer, and
t' equal thickness of each of the pieces of B,C, and D.

Then t' equals $\frac{T-2t}{3}$. Why?

Let W equal width of the block taken from the design of Prob. 12, and

A Mechanical Course For High Schools.

W' equal width of B,C, and D.
Then W' equals W-2t. Why?

Let H equal total height of block from base to vertex as taken from design of Prob. 18, and let

H' equal height of B,C, and D to their vertices.

Then H' equals H-t (if upper end of the block is square) and H' equals H- 2t (if the angle included between the upper faces is ninety degrees.) Why?

To determine the amount to be subtracted from H, for angles between these two values, use a graphical method with a scale several times full size, i.e. draw two lines, inclined at the proper angle, a distance apart equal to the thickness of the veneer, to the chosen scale, and measure the distance cut by these lines from any vertical line. This distance reduced to full size will be the required amount to subtract from H.

(NOTE:- In using formulas, all dimensions must be reduced to the same unit. Why?)

(b) Make each piece a true rectangle of dimensions W'xW' and of thickness t'.

(NOTE: - USE A SHARP KNIFE AND A STRAIGHT EDGE FOR LAYING OUT AND CUTTING ACROSS THE GRAIN OF THE WOOD. Use a gauge for lines with the grain. Leave the trace of these just showing on the finished pieces. Be sure that the surfaces of B,C, and D are plane surfaces, i.e. that when placed in any position, one upon another, a pressure exerted at the corners will produce no rocking motion.)

(c) Draw the vertical center line of each piece and, with a bevel, lay off in each case the angle of the top faces from the point at which the upper edge is crossed by this line. Finish the top edges.

(d) Make lead weight by filling a short section of light brass tubing with molten lead. Make the length of each weight 2t'.

(e) Locate a point on each center line a distance from the base equal to 1 1/2 times the diameter of the lead weight. With this as a center and, with an expansion bit set to the diameter of the weight, bore a hole completely through one piece and half way through each of the other two pieces. (See Fig. 2.)

Second:-

Glue together the pieces B,C, and D, having first inserted the lead cylinder as indicated in Fig. 2.

CAUTION: Clamp securely so that no slipping of the sections out of alignment will be possible. Use only the best of hot glue.

Third:-

Make the faces A and E with the grain of the veneer running vertically in each case.

(a) As in the case of the parts B,C, and D, first make A and E perfect rectangles of dimensions W'xH'.

(b) Draw center lines and lay off the angles of the top faces as before.

(c) Cut original design from front face, E as indicated in Fig. 1.

CAUTION: Keep the veneering firmly clamped between other heavier pieces, while performing the various operations to prevent its splitting. See that every tool employed is as sharp as it can be made.

Fourth:-

Glue A and E to the block formed of B, C, and D. Observe "Caution" of the second step.

Fifth:-

F and G will next be made. These side pieces also will have their grain extending vertically.

(a) First construct two rectangular pieces of veneer of width F and approximately one inch longer than the side of the block.

(b) At a distance from either end of block, equal to that of point E from the base, draw a line squarely across the inner face of each piece.

(c) Bisect the angle between either top face of the block and the vertical side adjoining it. Set the bevel to this angle and transfer it to the edges of F and G, i.e. let the head of the bevel rest against the outer faces and the edge of the blade pass through the ends of the lines drawn in step (b) while making the lines across the edges.

(d) Square across the outer faces of F. and G, through the upper points of the angles just transferred.

(e) Finish these upper edges exactly to line.

Sixth:-

Glue F and G in position. Observe "Caution."

Seventh:-

Make upper faces K and I with grain of veneer extending in the direction of the longest dimension.

(a) Construct two rectangular pieces of veneer of width T and approximately one inch longer than the distance from the vertex to the point E, i.e. one inch longer than either of the upper faces.

(b) Bevel one end of each piece to the same angle as that at the upper ends of F and G.

(c) At a distance from the inner edge of each of these bevels, equal to that from point E to the vertex of the block, draw a line squarely across the lower face of each piece.

(d) Bisect the angle included between the upper faces of the block. Transfer this angle to the edges of the pieces K and I, i.e. let the head of the bevel, which has been set to the

proper angle, rest against the upper faces of the parts H and I and let the edge of the blade pass through the ends of the lines drawn in step (c) while making the lines across the edges.

(e) Square across the upper faces of H and I through the outer points of the angles just transferred.

(f) Finish these ends exactly to line.

Eighth:-

Glue H and I in place. Observe "Caution."

Ninth:-

Make strip of base molding of ample length for the front and two sides of block as indicated at J,K and L. This will, of course, be made of the same kind of hard wood as the veneer.

(a) Square one end of the strip of molding and, at a distance T, draw a line squarely across the inner face of the molding. Cut a forty-five degree mitre through this line. See J of Fig. 1.

(b) In the same manner lay off the pieces K and L, making the inner face of K equal to J and that of L equal to T. See K and L, Fig. 1 for directions in which mitre is to be cut.

Tenth:-

Glue J,K and L securely in place. Observe "Caution."

A Mechanical Course For High Schools.

Eleventh:-

Sand paper the surfaces, using only fine paper, secured to a sand paper block. Be careful to round none of the edges. Do not sand across the grain of the wood.

Twelfth:-

Stain, fill and wax or shellac.

Thirteenth:-

Cut a piece of heavy felt to the exact size of the base of block and secure in place with cold glue.

NOTE: The two blocks of the set may be carried along in consecutive steps or may be completed separately as preferred.

Plate B of Course S1.

Plate B of Course S1 gives the details of construction of the tool chest designed in Prob. 13, D1. The parts, whose construction will herein be explained, are:

A.- Box cover, showing position of hinges and lock.

B.- End of box showing position of handle, dovetails, and rabbet to receive the bottom (D).



A MECHANICAL COURSE FOR HIGH SCHOOLS.
By Robert A Perkins.

PLATE B.	Wood Working. · Course S1 ·	DRAWN · BY · R.A.Perkins.

A Mechanical Course For High Schools.

C.- Front of box, showing lock, dovetail with blinds, and rabbet to receive the bottom D.

D.- Bottom of chest.

E.- End of tray showing corner construction.

F.- Side of tray showing corner construction and method of holding the bottom of tray, G.

G.- Bottom of tray.

H.- Strip secured to ends, and sides of chest to support the tray and to allow it to be moved from the front to the back of the box.

In building the chest the following steps will be taken.

First:-

Construct the sides and ends of the box of hard or soft wood, as directed by the supervisor.

See NOTE of step (b) of preceding problem.

(a) Let L equal total length of box taken from student's design of Prob. 18, Pl,
W equal width of box,
D equal depth of sides of box, exclusive of cover,
T equal thickness of sides and ends of box, and
t equal thickness of blind.
Then L' equals the length of the end pieces (B) equals W-2t. Why?

A Mechanical Course For High Schools.

Let t' equal thickness of bottom of chest
Then depth of rabbet equals 3t'/4 and bottom of box is set up a distance equal to t'.
By substitution determine the above dimensions.

(NOTE:- In using formulas, all dimensions must be reduced to the same unit. Why?)

(b) Make two rectangular pieces of dimensions LxD and thickness T and two of dimensions (W-2t)xD and thickness T. The grain of each piece is to run in the direction of its long dimension. Finish to these dimensions.

(c) The rabbet, to receive the bottom, will next be cut in these pieces. This is to be of width t', of depth 3t'/4, and is to be parallel to the lower edge and a distance t' above it. This may be made with a plow, may be cut with a dado saw, or may be cut out with a chisel, exactly as would be done in driving a mortise for a mortise and tenon joint.

(d) Lay out dovetails on end pieces B. These will be (T-t) in length and of width and taper indicated in the student's design. Saw just outside the lines running with the grain and chisel just outside those running across it. Finish exactly to the line with an extremely sharp chisel of a width as great as can be conveniently used.

(e) Lay out dovetails upon the ends of the sides (C). Check with those cut from B to be sure that no error has been made. Saw along the

lines extending in the direction of the grain, being careful, however, to hold the saw inclined at such an angle as to keep it from touching the blind. It will, of course, only be possible to cut the corners in this manner, but this will be found a great help when it comes to removing the remainder of the material with the chisel.

(f) Carefully fit each corner joint and assemble the sides and ends without gluing.

Second:-

Make the bottom of the box of hard or soft wood, as directed by the supervisor. The grain of this piece, D in the figure, is to extend in the direction of its long dimension. If the design calls for a large box, this may be glued up of two or more pieces.

(a) This piece will be of rectangular shape, its length being L-2(T-5t'/4), (Any?) and its width W-2(T-5t'/4), (Any?) Its thickness will be t'. Finish to these dimensions.

Third:-

Make the strips (H) of dimensions indicated in the design of Prob. 12, Dr. Cut as thick to be used with holes drilled for screws and counter-sunk for heads.

(a) Make two of these pieces of a length equal to the width of the inside of box, i.e. W-2T. Cut ends at forty-five degrees mitre as indicated.

(b) Make two of these pieces of a length equal to that of the inside of the box, i.e. L-2T. Cut ends at a forty-five degree mitre, as indicated.

(c) Secure these strips to the sides and ends of the box with screws and glue. The distance from the upper edge to each of the pieces (B) and (C) should be equal to the width of (B), which we will call (w).

Fourth:-

Glue the corner joints, first inserting the bottom in the rabbet provided for it. Do not glue the bottom into the rabbets. Why? Use hot glue only.

Fifth:-

Construct the sides (F) and the ends (E) of the tray. These are to be made of hard or soft wood, as directed by the supervisor, with the grain running in the direction of the long dimension of the piece in each case.

(a) Make joint at corner, as indicated, and make rabbet for bottom exactly as was done for the bottom of main chest. The width of each piece will be (w), the length of (E) will be the dimension given on the student's design, and the length of (F) will be L-2(T+t") where t" is the thickness of the blind of the corner joint. Why?

Sixth:-

Make bottom for tray exactly as was done in the case of the bottom of the chest, keeping in mind the changed proportions.

A Mechanical Course For High Schools.

Seventh:-

Glue the corners, first inserting the bottom in the rabbet provided for it. Do not glue the bottom. Why? Use hot glue.

Eighth:-

Make cover (A) of the same material as (B) and (C). The grain of this piece is to extend in the same direction as the long dimension of the box.

(a) The cover will be glued up of two or more pieces, depending upon the size of the box shown in the student's design, and will be finished a perfect rectangle of length L, width W, and of thickness indicated in the drawing.

Ninth:-

Place the two end hinges as indicated. A third hinge may be located exactly in the center of the cover if the design calls for a large box.

(a) These hinges are to be mortised so that the faces will be flush with the surface of the cover and the upper surface of the side of chest. Great care must be exercised to set hinges in exact alignment with each other and with the box. First secure the hinges in their correct position upon the box.

(b) After this has been done, close the hinges, place the cover in its position, and mark with knife blade the exact location of the hinges at the back edge of the cover.

A Mechanical Course for High Schools.

(c) Upon the inner face of the cover, square in from these points and cut mortise of correct depth and width.

(d) Screw hinges in position.

Tenth:-

Mortise lock in front (C) and in the cover (A) as indicated.

Eleventh:-

Mortise for handles slightly above the horizontal center line and exactly upon the vertical center line of the ends (B).

Twelfth:-

Sand paper all surfaces, using a sand paper block at all times. Do not round edges. Do not sand across the grain of the wood.

Thirteenth:-

Stain inside and outside. Fill and shellac or wax outside surfaces only.

Fourteenth:-

Screw handles in place.

Plate C of Course S1.

The next problem to be considered is that shown in Plate C of Course S1, which contains

Fern Box Detail.

Dimensions to be taken from Prob. 14
Course D1.



A MECHANICAL COURSE FOR HIGH SCHOOLS.
BY ROBERT A. PERKINS

PLATE		DRAWN
C	Wood Working · Course S1 ·	BY RAPerkins

A Mechanical Course For High Schools.

the details of construction of the form box, designed in Prob. 14, Pl. The parts shown, whose construction will later be explained, are:-

A.- End of box and vertical support or standard.

B.- Base block.

C.- Cross braces.

D.- Sides of box.

E.- Bottom of box.

F.- Sheet zinc earth retainer.

G.- False bot om to allow excess water to drain.

H.- Vertical openings of rectangular shape to lighten the appearance of the parts.

I and J.- Mortise and tenon securing end to base block.

K.- Dovetail joints.

L.- Mortise to receive cross braces.

M.- Rabbet to receive bot om of box.

The outline of the steps to be taken in constructing the form box is as follows:

A Mechanical Course For High Schools.

First:-

Make the two side pieces (D) of hard or soft wood, as directed by the instructor, with the grain running in the direction of their length.

(a) Let L equal total length of box, taken from student's design,
W equal width of side,
T equal thickness of side, and
t equal thickness of bottom.
Then depth of rabbet equals 3t/4.
Distance of rabbet from the bottom edge of side equals t.
Length of rabbet equals L-4(T)
Length of dovetails equal T.
By substitution, determine the above dimensions.

(b) Make two rectangular pieces of length L, width W, and thickness t.

(c) Plow, saw or chisel rabbet at the lower edge of each piece, making its width t, depth 3t/4, and its distance from the edge t. Its length will be L-4T and will be centrally spaced.

(d) Lay out and cut dovetails at ends as designed in Prob. 14, Pl.

(e) Cut openings (H) according to design. Lay out carefully upon both inner and outer faces of the side, using guage, knife and square. With brace and bit, bore hole at upper and lower ends of the portion to be cut away.

Saw well inside the lines, removing the material between the two holes. Bring exactly to the line by use of sharp chisel, working from both inner and outer faces.

Second:-

Make two end standards (A) of same material.

(a) Let H equal total height of table, including base, taken from the student's drawing,

h equal height of base block,
l equal length of tenon,
w' equal width of end at top, and
W" equal width of end at bottom.
Then L' equals H-h+l where L' equals length of end standards (A).
Thickness of tenon equals T-1/4"
Length of tenon equals W"-1/2"
By substitution determine the above dimensions.

(b) Make two rectangular pieces of length L', width W", and thickness T.

(c) Lay out and form the tenons (J) of thickness (T-1/4") and length (W"-1/2") symmetrically located with respect to the axes of the main piece. It is always well to have the surface separating any piece from its tenon slightly dished toward the tenon. This will insure the pieces resting squarely upon the one to which it is attached and will provide a small space for glue when pieces are tightly clamped together.

A Mechanical Course For High Schools.

(d) Lay out upon both surfaces of the parts (A), the openings (K), rabbets (M) and mortises (L). It is more convenient to do this drawing before the end supports are cut to the form of the design.

(e) Cut the end pieces (A) to form indicated in student's design and lay out and cut dovetails as explained in first step, part (3) of the preceding problem.

(f) Complete operations laid out in step (d). Work to the line from both sides of the pieces in finishing.

Third:-

Make base blocks (B) of same material as other completed parts.

(a) First make two rectangular prisms of dimensions, indicated in design of Prob. 14, D1.

(b) Lay out upon the upper and lower faces of these pieces, symmetrically placed, rectangles of width (2-1/4") and length (7-1/2"). Remove the material within these by chiseling from both surfaces.

(c) Lay out curve of portion to be removed from lower surfaces. Saw this out and finish to line.

(d) Chamfer edges as indicated.

A Mechanical Course For High Schools.

Fourth:-

Glue base blocks to end standards.

Fifth:-

Make cross braces (C).

Sixth:-

Make bottom (E) of white pine or bass wood.

(a) First make rectangular piece of length L-2(T-3t/4) and width W'-2(T-3t/4).

(b) Cut corners as indicated.

Seventh:-

Assemble and glue parts together.

Eighth:-

Sand and finish as in preceding exercises. Do not round corners and do not sand across grain.

Ninth:-

Have "retainer" constructed by students of Course S9. In case this course is not yet in effect, it will, probably, be necessary for the pupil to have this constructed by an outside mechanic, although the pupil should make the exact patterns to which the sheet metal is to be cut.

A Mechanical Course For High Schools.

Tenth:-

Paint outside surface of work so that portions showing through openings (H) will present a neat appearance.

Plate D, Course S1.

In Plate D, the details of the tabouret e designed in Prob. 15, D1, are shown, together with an explanation of the letters of reference.

In its construction the following outline will be observed:

First:-

Make upper cross braces (C) of hard or soft wood as directed.

(a) Let W equal distance across faces of square, from which top is made,
W' equal distance across top from face to face, formed by cutting corners of square to receive legs of tabouretie,
T equal thickness of legs, braces, and top,
w equal width of braces, and
L equal length of upper braces over all.
Then $\frac{L-W'+3/8"}{2}$ equals distance from each end of upper brace to upper edge of shoulder.
Let t equal thickness of key
Then width of tenon equals 3t.
Obtain values of above terms by substitution.



FIG. 1



FIG. 2

TABOURETTE.

No glue is necessary in this exercise as all the joints are secured mechanically.

EXPLANATION.

A.- Tabourette top. May have border pieces A, if desired
B.- Leg design.
C.- Upper cross braces.
D.- Lower cross braces.
E.- Keys for holding legs to braces.
F.- Keys for holding border to main part of top.

A MECHANICAL COURSE FOR HIGH SCHOOLS.
By Robert A. Perkins

PLATE		DRAWN
D.	WOOD WORKING · COURSE S1 ·	By. R.A.P. Perkins

A Mechanical Course For High Schools.

(b) Make two pieces of length L, width w, and thickness T with grain run ing longitudinally.

(c) Assuming 3/16" as depth of dado, lay out tenons on upper surface of each piece, making length $\frac{L-w'+3/8"}{2}$, and width St. Set bevel at angle of slope of legs, as taken from design of Prob. 15, Dl. Lay this angle off upon each edge, so that the length of the tenons will be slightly less at the bottom than at the top of each piece. Saw out and finish tennons.

(d) Make half-lap joint, so that the two pieces will be at right angles, will have their upper and lower surfaces flush each with the other, and each will have its center line bisected by that of the other.

(e) Chamfer ends of tenons as indicated.

Second:-

Construct lower braces (D) of same material as (C).

(a) Let D equal distance between the upper faces of the two sets of braces as taken from design and,
p equal pitch or slope of legs.
Then length of lower braces equals L+2Dp-3/8". Why?

(b) Make two pieces of length L+2Dp-3/8", width w, and thickness T with grain run ing longitudinally.

(c) Lay out and construct tenons exactly as was done in the case of the upper braces.

(d) Lay out curves, reducing the width of braces as indicated, and finish to these lines.

(e) Make half-lap joint as in the case of the upper braces, keeping in mind, however, the decreased width of the members.

(f) Chamfer ends of tenons as indicated.

Third:-

Make the four legs (B) of same material as (C) and (D), with the grain running longitudinally.

(a) Construct four rectangular pieces of width W, thickness T, and length, approximately, one inch longer than the legs are shown in the design of Prob. 15, D1.

(b) Set bevel to angle included between upper face of brace and any of the inclined cuts. Transfer this angle to the upper end of each of the pieces (B), laying it out along the edge, so that the angle will be included between the outer and upper faces after cutting to the line.

(c) Transfer this angle to each of the lower ends so that the angle will be included between the inner and lower faces after cutting to the line. The upper and lower faces should now be parallel and the distance between them equal to the length of leg called for in the design of Prob. 15, D1.

A Mechanical Course For High Schools.

(d) Chamfer upper ends as indicated.

(e) Lay out upper and lower mortises, locating same as indicated in design. The vertical distance between corresponding surfaces of these mortises will be D, their length St, and their width T. These mortises must be carefully drawn upon both the outer and inner faces of the legs. To do this, first locate openings centrally upon the outer faces; next, square across these outer faces at the levels of the upper and lower lines of each opening; then, with bevel carry these lines across the edges of the legs, parallel to the lines of upper and lower ends; finally, carrying them squarely across inner faces and locate vertical lines of width opposite those upon the front surface. In driving mortises, work from both faces of legs.

(f) Cut legs to form shown in student's design.

(g) Cut dado across upper end of each leg to receive top. The bottom surface of this will be flush with upper surface of mortise. Its upper surface will be a distance T above this and parallel to it. The depth will be 3/16" at top. Will its depth be more or less at the bottom edge?

Fourth:-

Assemble, temporarily, the braces and legs.

Fifth:-

Make keys of thickness t and of length and taper shown in design.

A Mechanical Course For High Schools.

Sixth:-

Lay out key-ways.

(a) Hold key against side of each tenon and against outer surface of leg in the vertical position that it will occupy in the key-way, i.e. place it with its transverse center line along the longitudinal center line of the edge of tenon. Make line along its outer edge upon side of tenon. Also make line along face of leg upon all faces of tennons.

(b) Square across upper and lower faces of tenon through the upper and lower ends of the line drawn along the edge with the key as a guide.

(c) Remove legs from braces. With guage draw line parallel to each of the edges of tenons and a distance t from them. These lines meet those drawn across the upper and lower faces and form a small rectangle upon each; that upon the lower face being the shorter.

(d) Remove the material from these by chiseling from both upper and lower surfaces.

Seventh:-

Make top of a single piece or of central piece with border as indicated in Fig. 2.

(a) In case top is made of one piece, first make square with sides W and thickness T. Draw diagonals. From their point of intersection, lay off a distance W'/2 upon the diagonals and construct perpendiculars to them at the points thus determined. Cut corners to these lines.

(b) In case border is used, follow construction shown in Fig. 2.

Eighth:-

Sand paper each part. Use block so that edges will not be rounded. Do not sand across grain.

Ninth:-

Stain and fill all parts.

Tenth:-

Assemble the tabourette.

Eleventh:-

Shellac or wax as preferred.

Plate E of Course S1.

The drafting table designed in Prob. 16, D1, is next shown in detail. This will be found in Plate E, the parts to be explained are:-

A.- Base block (Fig.1)

B.- Vertical support (Figs. 1 and 2.)

C.- Sliding member of vertical support (Figs. 1,2, and 3.)

D.- Side guides (Figs. 1 and 2.)

E.- Cross braces (Figs. 1 and 2)


Fig. 2
C.
C.
D.
B.
D.
G.
F.
C.
D.
D.
E.
E.
D.
B.
A.
Fig. 1
Fig. 3
H.
H.
H.
L.
H
G
J.
F.
H.
O
O
H.
Fig. 4
A Mechanical Course for High Schools.
By Robert A Perkins.
Plate E
Wood Working
Course S1
Drawn by R.A. Perkins

A Mechanical Course For High Schools.

F.- Lock nut for holding adjustment of inclination of table top. (Figs 1 and 3.)

G.- Lock nut for holding vertical adjustment of table top. (Figs. 1 and 2.)

H.- Cross pieces of top. (Figs. 3 and 4.)

J.- Adjustment rod. (Fig. 3.)

K.- Sections of table top. (Figs. 3 and 4.)

L.- Strips holding the sections K. (Fig. 3)

All wooden parts with the exception of the top pieces K are to be made of clear red oak, white oak or birch. The top will be made of clear white pine.

First:-

Make the two base blocks (A) with the grain of the wood running horizontally.

(a) Let H equal height of vertical supports including base blocks,
h equal width of cross braces (E),
h' equal height of base blocks,
l equal length of tenons,
T equal thickness of base blocks, and
L equal length of base blocks,
Then length of pieces B equals H-h+l and thickness of tenon equals T-3/4".
Let w equal width of B
Then width of tenon equals w-1/4"
Determine these dimensions by substitution.

(b) Construct a rectangular prism of length L, thickness T and width h'.

(c) Lay out, in a central position, upon both the upper and lower faces, a rectangle of length w-1/4" and width T-3/4". Chisel mortise of this size through the block, driving it from both faces.

(d) Shape ends and cut out bottom portions according to student's design in Plate 16, D1.

Second:-

Construct vertical standards (D) with grain running vertically.

(a) Make two rectangular pieces of length L, width w and thickness T.

(b) Construct tenon of length l, width w-1/4" and thickness T-3/4", centrally located at the lower end of the piece D.

(c) Lay out the distance h, i.e. the height of braces (E) from the base line of vertical supports, as indicated in Fig. 1, Plate E. Square along the edges and across the inner face at this level. Gauge a line, a distance T/2 from either the front or back face, along both edges and across the top. Cut out the portion within these lines at the back of each piece as indicated. Finish accurately to the line.

(d) Make vertical slot. To do this, lay out with guage and square on both inner and

outer surfaces. Bore hole at top and bottom ends and saw out material between. Finish exactly to line on both faces.

Third:-

Make side guides (D).

(a) These will simply be rectangular pieces of length H-(h+h'), width B and thickness T/8.

(b) Drill for screws and counter-sink for screw heads.

Fourth:-

Make cross-braces (E).

(a) These will also be rectangular pieces of length indicated upon design of student's plate 16, D1, width h, and thickness T/8.

(b) Drill for screws and counter-sink for heads.

Fifth:-

Make the sliding members (C).

(a) These will be of length indicated in design, of width w, and thickness T/8. The ends will be semi-circular and will be drilled to receive bolt holding top. The lower portion will be slotted, as shown, to allow of greater adjustment than would otherwise be possible.

(b) Attach the lock bolt and plate as indicated. This consists of a square-headed bolt which is mortised in from the outer face of C.

A plate, drilled and counter-sunk for four screws, is drilled and tapped to screw on over this bolt. The screws are then inserted at the corners, thus holding the bolt firmly in place. These pieces are to be made in the metal working shops, together with the pieces (J) and (G), and the clips holding the top sections to cross pieces (H).

Sixth:-

Make the cross pieces (H).

These will be the dimensions shown in student's design. The groove for holding ends of clips, as indicated in Figs. 3 and 4, are kerfs of a circular saw.

Seventh:-

Make top. This will be of dimensions indicated in student's design and will be glued up of several sections (K) as shown in Figs. 3 and 4. The rabbets for receiving the strips (L) may be made with dado saw or plow. Plane, scrape, and sand the top to a smooth and even surface.

Eighth:-

Assemble the various parts, first carefully sanding each piece as in previous exercises. Do not round corners or edges. Do not sand across grain.

Ninth:-

Scrape off any excess glue and then stain, fill and varnish or wax all hard wood parts. Shellac the top without staining.

A Mechanical Course For High Schools.

Plate F of Course 81.

The next problem of the series is that of the screen designed in Prob. 17, D1. This is to be constructed of red oak, white oak, or birch. The features shown in detail are:

A.- Ornamental shelf.

B.- Upper rail, showing tenons and manner in which it is cut to receive bracket and shelf.

C.- Bottom rail, showing tenons and mortise for vertical strips. The upper rail is mortised in exactly the same way.

D.- Brackets supporting shelf.

E.- Corner members, showing mortises and chamfer at upper and lower ends.

F.- Vertical strips.

The construction of this exercise is, apparently, simple, but its many joints that must be accurately fitted make it much more difficult than appears at first glance. The outline for its construction is as follows:

First:-

Make corner members (E).

A MECHANICAL COURSE FOR HIGH SCHOOLS
By Robert A Perkins

PLATE.	Wood Working · Course S1 ·	DRAWN BY
F.		RAPerkins

Note:—The screen is to consist of at least three sections as designed in D1. It may be covered with burlap stretched across the back if desired



A Mechanical Course For High Schools.

(a) These will be of square cross section and of dimensions indicated in student's design of Prob. 17, Dl. The ends will be chamfered as indicated.

(b) Let T equal thickness of rails (B) and (C),

W equal width of (B)

W' equal width of (C)

H equal distance between upper edge of (C) and lower edge of (B),

w equal width of vertical pieces (F),

t equal thickness of vertical pieces (F)

Then thickness of tenons equals T-1/4"

Width of tenons for (B) equals W-1/2"

Width of tenons for (C) equals W'-1/2"

Distance between lower edge of upper tenon and upper edge of lower tenon equals H+1", and,

Depth of mortises in (B) and (C) to receive vertical strips equals 5t/4.

Obtain the above dimensions by substitution.

(c) Make mortises of width T-1/4", length W-1/2", and depth three-fourths of width of (B) for upper rails (B). These are to be centrally located at a distance from the top equal to that shown in design.

(d) Make mortises of width T-1/4", length W'-1/2" and depth as for upper mortises. These are to be centrally located and are to be placed so that the upper face will be a distance H+1" from the lower face of the upper mortise.

A Mechanical Course For High Schools.

Second:-

Make upper and lower rails. These should be laid out in pairs, i.e. should be cut to the same length and should be clamped together with ends flush when laying out mortises for vertical pieces (F) and the tenons securing them to the corner members (E). The length of these mortises will be w, width t, and depth 5t/4. The width of tenons will be W-1/2" for upper rails and W'-1/2" for lower rails. Their thickness will be T-1/4" and their length t/4 the width of (E).

Third:-

Make vertical strips (F).

(a) These will be rectangular pieces of length H-1 1/2 t, and width w, and thickness t.

(b) The ornamental openings will be laid out upon both inner and outer faces of the strips; holes will then be bored at the upper and lower ends and the material between removed by sawing well within the lines; and, finally, the edges will be brought to line with a sharp chisel, working from both inner and outer faces.

Fourth:-

Make shelf and brackets (A) and (B) and fit same in exact center of upper rail of middle section of screen.

Fifth:-

Scrape and sand all surfaces, using extreme care to round none of the edges. Do not sand across grain.

A Mechanical Course For High Schools.

Sixth:-

Assemble and glue all joints. Square all corners and clamp firmly in place while glue is setting.

Seventh:-

Remove glue that has been forced from joints. Stain, fill, shellac and wax or varnish as preferred.

Eighth:-

Nothing has been said regarding the hinging of corners as this may be done with leather straps, allowing the sections to swing into any desired position, or they may be secured by mortised hinges, which allow adjustment in one direction only.

Ninth:-

Burlap may be stretched across the back face of the screen and attached to the upper and lower rails and corner posts by small strips and screws. This gives a very pleasing effect and affords a more perfect screen.

Plate G of Course S1.

The last three problems of Course S1 are taken from the supplementary problems of Course D1. The first, detailed in Plate G, is the drawing board and drawer, designed in Optional Prob. No. 1. The parts shown are:

A Mechanical Course For High Schools.

A.- Top glued up of several sections, reinforced by strips rabbeted into adjacent pieces.

B.- End pieces secured by tongue and groove joints to A.

C.- End of cabinet.

D.- Frame work of bottom and drawer supports.

E.- Drawer front, showing blind dovetail, corner joint and handle.

F.- Bottom of drawer which fits into rabbet of sides and ends of drawer.

G.- Side of drawer, showing dovetail joint at corner. All corners are to be constructed in the same manner.

H.- Bottom of cabinet. This fits into rabbet made to receive it in the piece D.

I.- Upper drawer guide.

J.- Birch strip secured to C by screws and glue. Screws passing through slots shown at the upper surface hold A in position.

K.- Back side of cabinet.

L.- Back side of drawer.

The outline of the construction is as follows:



NOTE:- This exercise is to be constructed from drawings of optional problem No I, D1.

A MECHANICAL COURSE FOR HIGH SCHOOLS. By Robert A Perkins		
PLATE G	WOOD WORKING · COURSE S1 ·	DRAWN BY R.A.Perkins

A Mechanical Course For High Schools.

First:-

Make ends of cabinet (C). The cabinet will be constructed of hard or soft wood as directed by the supervisor. The parts (A), however, will be of clear soft white pine.

(a) Lay out and cut to dimensions indicated in design made by the student in his Plate No.I D1. The grain of the wood is to run horizontally in the finished piece.

(b) Make blind dovetail joint at back corners. The construction of these joints is clearly shown in Plate B, S1, and its construction is explained in the accompanying text.

Second:-

Make back side of cabinet (K) of same wood as C with its grain running in the direction of the long dimension of the piece.

(a) Let L equal length of cabinet as taken from design

T equal thickness of sides, ends, etc.,
t equal thickness of blind end,
t' equal thickness of bottom pieces of cabinet and drawer.

Then length of K equals L-2t.

Determine this value by substitution. Remember that in substituting in formulas, all dimensions must be reduced to the same unit.

(b) Make rectangular pieces of length L-2t, width equal to C at its widest point, and thickness T.

(c) Lay out dovetails and check with those of (c). Cut out and finish as explained in Plate D,S1.

(d) Plane off top surface to correspond to slope of ends (c).

Third:-

Construct frame work (D) with corner construction as indicated.

(a) Make strip of thickness T, width 5T, and of length sufficient to make entire frame work with allowance for waste in making corners.

(b) Plow or cut with dado saw, a rabbet the entire length of piece; the depth of this to be 5t'/4 and its width t'.

(c) Cut two pieces of length L-8t and two pieces of length L'-T where L' equals length of the ends (C). Frame and fit corner joints as plainly indicated.

Fourth:-

Make bottom (E). This will be of length L-8T-1 1/2 t' and of width L'-7T-1 1/2 t'.

Fifth:-

Screw and glue the pieces (D) to the ends (C), making the bottom face of (D) exactly flush with the bottom edge of (C). The back end of (D) will fit in a distance T from the back edge of (C). Use hot glue for all construction.

A Mechanical Course For High Schools.

Sixth:-

Glue dowels into the parts (D) which were fastened to (C) in step 5.

Seventh:-

Insert the bottom (H) into the side pieces (D) of bottom frame work and, with glue upon the corner joints, fit, at the same time, the parts (D) and (H) together and clamp securely while glue is setting.

Eighth:-

Insert the back piece (K), clamping and gluing it to the ends (C) and frame work (D).

Ninth:-

Make top (A) of clear white pine with joints constructed as indicated. The rabbets may be made with plow or dado saw as most convenient.

(a) The length of the pieces (A) will be L-2T, total width of top L; and the thickness 1/4" greater than that of (D).

(b) Reduce the back edge of the upper piece of (A) to the thickness of (B) for a distance T in from the back face of (K).

Tenth:-

Make end strips (B) and secure to (A) by rabbet and tenon as indicated. The upper face of (B) is to finish exactly flush with that of (A).

A Mechanical Course For High Schools.

Eleventh:-

Glue and clamp the pieces (A) and (B). Scrape, sand and shellac.

Twelfth:-

Make birch strips (J) of thickness T and depth 1 1/4" at back end and tapered to 0 at the front edge. Keep at full width as far as possible without interfering with the side of drawer.

(a) Drill two holes closely together, in sets as indicated and of a diameter equal to shank of screws to be used in screwing the parts (J) to top (A). Cut out the material between the holes, thus forming a series of slots running vertically through strip.

(b) Attach these to top with screws only.

Thirteenth:-

Make the pieces (I) of thickness T and of the proper pitch so that when glued over the strips (J) a level guide will be afforded for the upper surface of the side of drawer.

Fourteenth:-

Place the top in position and drill several holes through the ends (C), into the pieces (J). The drill is to be of size of shank of screws, going through (C) and of considerably smaller diameter going through (J). Countersink for screw heads and drive all screws.

A Mechanical Course For High Schools.

Fifteenth:-

Take out the screws, remove the top, and glue and clamp (I) into its position upon (J).

Sixteenth:-

After glue has set in step 15, remove clamps, place a film of hot glue upon outer surface of (I) and (J), as well as along the upper edge of (H), and replace top and again drive screws into place. Clamp firmly at back edge until glue has set.

Seventeenth:-

Plant a molding in corner formed by (C) and (B) to cover screw heads. This molding is not shown, but may be either a quarter-round or cove.

Eighteenth:-

Construct the drawer. As no operations, not already explained, are involved, no detailed explanation of its construction should be necessary.

Nineteenth:-

Sand all surfaces. Use sand paper block, so that rounding of corners may be avoided. Do not sand across grain of wood.

Twentieth:-

Stain, fill and shellac or varnish, all except top which is to have shellac finish only.

Twenty-First:-

Attach handle at center of front face of drawer.

A Mechanical Course For High Schools.

Plate H of Course S1.

Plate H shows in detail the construction of the second optional problem of Course D1, which is that of designing a draftsman's stool.
The parts detailed are:-

A.- Seat, showing mortises for ends of legs, chamfer of upper edge, and slightly dished upper surface.

B.- Legs of stool, showing tenons for securing them to top, mortises for cross braces, and chamfer of edges. The manner in which lower ends are tapered is also shown.

C.- Cross braces, showing manner in which they are staggered.

The outline of the steps to be taken in the construction of the st ol is as follows:

First:-

Make top of stool of clear red oak, white oak or birch.

(a) Let T equal thickness of seat,
D equal diameter of seat,
H equal total height of stool, including seat,
t equal thickness of cross braces,
W equal width of cross braces, and
w equal width of faces of legs.
Then length of legs equals H-3/8"
Depth of mortises in seat equals T-3/8"
Depth of mortises in legs equals w-3/8"
Obtain above values by substitution.





NOTE:- OPTIONAL PROBLEM No.2 IS HERE SHOWN.

A MECHANICAL COURSE FOR HIGH SCHOOLS
· BY ROBERT A PERKINS ·

PLATE		DRAWN
H.	WOOD WORKING · COURSE S1 ·	· BY · R.A.P. Perkins

A Mechanical Course For High Schools.

(b) Glue up the top of four pieces as indicated, the grain in each running longitudinally. The seat, as first glued together, should form a square of size D+1" and of thickness T.

(c) Dress to a smooth surface and lay out circles of outside edge, edge of chamfer, and line of dished portion.

(d) Saw out and finish to line, chamfer edge and work out dished portion. Of course, the quickest way to finish seat would be at the lathe, but, for this exercise, we prefer that all work be done by hand.

(e) Make mortices of depth T-3/8" and 1" square. (Note angle in second step.)

Second:-

Make the four legs (B) of close grained oak, white oak or birch.

(a) Make four pieces of length H+1/2" and of square section W. 7/8" is allowed for waste in cutting.

(b) At this point the only difficulties of the problem present themselves, viz. determining the angles of the various horizontal and vertical cuts. It will be noted that since the seat is horizontal and the floor upon which the stool stands is also horizontal, the upper end of the tenons and upper and lower ends of legs must be cut at an angle that will allow them to lie completely in these planes. It will further be noted that the legs, being further apart at the bottom than at the top, make

it necessary not only to have longer braces at the bottom of the stool than at the top, but also that the ends of braces be cut at such an angle as will permit them to enter the legs to an equal depth at all points. Finally, it will be noted that, since the braces are rectangular in cross section, and since their outer surfaces are placed parallel to the outer faces of legs, the upper and lower edges of mortises will be perpendicular to these outer faces. The mortises must be driven at the proper angle to accommodate these braces.

The determining of these angles will necessarily be an individual problem, dependant upon the student's design and will, therefore, be worked out graphically by each individual with the assistance of the instructor.

(c) Cut to length at the angle determined in (b). Make tenon of length 2-3/8", and of 1" cross section.

(d) Locate mortises for braces as in design. These are of width t, length W, and depth w-3/8" and are to be driven at the angle determined in step (b).

(e) Chamfer edges and cut taper at lower end of legs as indicated.

Third:-

Make braces. These are to be made of clear red oak, white oak, or birch. These will be of width W, thickness t. Their length must be determined by adding 2(w-3/8" to the apparent

length, taken from design, and by correcting for the angle determined in step (b) of the preceding section.

Fourth:-

Sand all surfaces. Do not round edges. Do not sand across grain of wood.

Fifth:-

Glue and clamp in assembled position.

Sixth:-

Remove any glue that may have been forced from joints by clamping.

Seventh:-

Stain, fill and varnish.

Plate I of Course S1.

The last problem of Course S1 is presented in Plate I. It shows, to a fairly large scale, the important parts of the serving table, designed in Optional Prob. III, Course D1. The parts shown are:-

A.- Table top with two hinged leaves.

B.- Fixed legs of table.

C.- Swinging legs of table. These support the leaves when raised and may be swung back under the table when the leaves are lowered.

D.- Lower longitudinal braces.



A MECHANICAL COURSE FOR HIGH SCHOOLS.
By Robert A Perkins

PLATE	Wood Working.	DRAWN
I.	Course S1.	BY RAPerkins

A Mechanical Course For High Schools.

E.- Upper longitudinal braces and supports for top.

F.- Upper members, holding swinging legs in position.

G.- Lower members, holding swinging legs in position.

H.- Lower transverse braces.

I.- Upper middle transverse braces.

J.- Lower middle transverse braces.

K.- Cross braces. A single piece may be used as indicated in Shop Sketch of Optional Prob. III, if preferred.

L.- Upper transverse braces.

In constructing this table, the following brief outline will prove helpful. As there are no operations in the building of this problem, not already explained in previous problems, all descriptive details are omitted.

First:-

Make table legs (D) and (C). These may be made of a single piece or be glued up of several laminations of hard or soft wood, as directed by the supervisor. In making mortises, remember that outer faces of (D) and (H) must be in the same vertical plane. Why?

Second:-

Make braces (D) and (E). Note that the

pieces (D) are slightly longer than the pieces (E) and that the ends of (D) are cut at an angle slightly less than a right angle, due to the taper for the legs. These braces are to be made of same material as legs and secured to them by mortise and tenon joints.

Third:-

Make braces (L) and (H).

Fourth:-

Make braces (I) and (J). These will be secured to the longitudinal braces by dowelled joints. The dowels should not penetrate (D) and (E) to more than three-fourths of their thickness.

Fifth:-

Glue and clamp the parts (B), (D) and (E).

Sixth:-

After glue has set in the above operation, glue and clamp (L), (H), (I) and (J) to the parts already assembled. It will be necessary to insert these pieces at the same time.

Seventh:-

Make the cross braces (K) with half-lap joint at their common center, as indicated. Secure these in position between the parts (I) and (J) by gluing and by the use of screws, whose heads have been counter-sunk and covered.

A Mechanical Course For High Schools.

Eighth:-

Make braces (F) and (G) and secure them to the legs (C) by mortice and tenon joints. The tenons of (F) should be secured in position, in addition to gluing, by the use of dowels passing through the tenon and the sides of legs. These, being cut flush and finished with the leg, will not be noticeable.

Ninth:-

Hinge (F) and (G) to (D) and (E) as indicated.

Tenth:-

Make table top. This must be glued up of several sections, well jointed and carefully selected as to grain, color, etc. Glue up each of the leaves and the center portion as separate pieces and fasten them together, temporarily, by cleats tacked across their bottom faces. Lay out circle of top and with band saw, saw just outside the line. Finish to line, dress to an even surface and scrape. Hinge the three top sections as indicated. The wood used should be the same as for the remainder of table.

Eleventh:-

Sand all surfaces till clean and smooth. Use great care not to round corners and not to sand across grain of wood.

Twelfth:-

Stain and fill.

A Mechanical Course For High Schools.

Thirteenth:-

Attach top to the braces (L) and (L) by metal clips or angles.

Fourteenth:-

Varnish and rub to an egg shell gloss with pumice stone and oil.

A [illegible] [illegible] [illegible]

TABLE OF CONTENTS OF BOOK V.

COURSE 28.

	Page
Introductory Remarks.....	1 - 3
Instructions for Exercise No. 1, Plate 1..	3 - 6
" " " " 1, " 2	6 - 9
" " " " 1, " 3	9 -11
" " " " 1, " 4	11 -15
" " " " 1, " 5	15 -18
Exercise No. 1 of Course 28.....	18

LIST OF ILLUSTRATIONS
OF
CABINET WORK.

	Page.
Details of Desk, with Lamp...	2
Hall Table Lamp Details.....	7
Combination Chair and Table Details.....	9
Work Bench Details.....	12
Hall Clock Section and Elevation.....	16

A Mechanical Course for High Schools.

WOOD WORKING.

Course S2.

Course S2 is to be considered simply a continuation of Course S1. The additional exercises for the course are to be a selection of any one of those shown in Plates A to L, included herewith, together with the cabinet designed in Plate III, D2. These two exercises must be most carefully executed, both in design and construction. Especial attention is to be given the processes of staining, filling and rubbing in order that the finish of the completed exercises will have a distinctly elegant appearance. No exercise showing carelessness in design or execution will be accepted for credit in this course.

The Plates, referred to above, detail the construction of the last three exercises of Course D1, regular and optional problems included, and the accompanying text is descriptive and explanatory of them.


A MECHANICAL COURSE FOR HIGH SCHOOLS.
BY ROBERT A PERKINS.
PLATE A
WOOD WORKING
COURSE S2
DRAWN BY R.A.Perkins
P.
O.
P.
O.
Q.
S.
B.
B.
T.
R.
A.
C.
M.
B.
M.
N.
N.
I.
H.
A.
D.
F.
L.
F.
E.
K.
U.
I.
J.
D.
G.
G.

A Mechanical Course For High Schools.

Plate A, Course 3S.

In Plate A, Course 3S the details of construction of the desk with lid ht, designed in Prob. 18, D1, are shown descriptively projected. An explanation of the letters of reference follows:

A.- Desk top. This is to be glued up of several sections of a select hard wood, carefully matched as to color, grain, etc.; accurately jointed, glued and clamped; and finally, planed, scraped and sanded to a smooth and even surface.

B.- Back of desk. This is made in two parts, if lamp is included in the design, and, of course, is one continuous piece if lamp is omitted. Each part will be cut away to receive the metal pieces ( ) and will be secured to the table top with screws and glue as indicated.

C.- These will be mortised to receive the frame work of table as shown, and be secured at their upper ends to the side members (I), not shown, by mortise and tenon joints.

D.- Front and back frame work for drawer guides. The manner in which these pieces are secured to the legs, to the side frame (I), and to the vertical members (F) and (G) will be carefully noted.

A Mechanical Course For High Schools.

L.- Drawer supports.

F.- Back vertical members supporting lower shelf. These will be set into shelf in exactly the same way as indicated in D and glued in position.

G.- Front vertical members. Similar to F with the exception that portions are cut away to lighten their appearance.

H.- Back of drawer cabinet. The sides of the cabinet will be constructed in exactly the same manner, each piece being secured to the legs by a mortise and tenon joint and to the parts D,L and I by the use of screws and glue.

I.- Top member of desk for the work. This member is to set flush with the back edge of top, but at the ends and front edge, the top will be allowed to overhang a distance and beveled to allow of a moulding being placed as indicated. As before stated, the legs will be secured to this member by mortise and tenon joints and the top by screws and glue.

J.- Drawer front, showing style of drawer pull and rabbet to receive bottom. Blind dovetail joints will be used at the front corners of drawer and simple dovetail joints at the back. (See Plates B and C, Bl.

M.- Drawer bottom.

A Mechanical Course For High Schools.

L.- Drawer back.

M.- Rack for holding stationery and letters. The pieces (M) will be secured to parts (L) and (D) by glued joints, reinforced by screws, driven from their lower and back faces, respectively.

N.- Sliding member of lamp.

P.- Lamp support. This passes through mortise in O, made to receive it with an exact sliding fit.

Q.- Metal guides. These will be made in the horse shop from patterns furnished by the student for which desk they are to be used. The drawing shows clearly the manner in which these are bent to form guides for O, as well as the placing of a machine-screw holes for securing them to the parts (K) and (D).

R.- Front member of lamp standard. This will be mortised into the top (A) as indicated.

S.- Bolt for clamping O to the metal guide (Q).

T.- Side members of lamp standard.

U.- Drawer guide. This may be fitted in rabbet as indicated or may be glued into the corner formed by the members (D) and (K).

A Mechanical Course For High Schools.

If the pupil desires to do so, the design of this exercise may be simplified, with the consent of the supervisor, by omitting the lamp.

Plate I, Course 22.

The details of construction of the table lamp designed in Prob. XXXI,D1, are here shown, the parts detailed being as follows:

A.- Lower member of base. It will be noted that a thin strip with its upper edge chamfered at forty-five degrees is planted around the edge of the entire piece. This covers the end grain of (A).

B.- Upper member of base. This is of similar construction to that of (A) and is secured to it by screws and glue as indicated.

C.- Corner braces. Secured to (B) by screws and glue.

D.- Vertical corner members. These are complicated in form and difficult to make, for the angles formed by the various surfaces must be accurate in order that perfect joints with the lower guide (G) and the panels (E) may be secured.

E.- Panels. These should be glued up of from two to three laminations of veneer ply.



A MECHANICAL COURSE FOR HIGH SCHOOLS.
By Robert A. Perkins.

PLATE		DRAWN
B.	WOOD WORKING · COURSE S2 ·	BY R.A.P.

A Mechanical Course De Work Sche le.

D.- Cross sup orts for shade, should ornamental cut of style, gain for half-lap joint at middle of cross supports, and mortise to receive the pieces (E).

C.- Lower p rt of panel. This is rabbeted to receive (B) and is secured to the corner members (D) by mortise and tenon joints. It will be seen that the corners of the panels (B) are cut at forty-five degre s to allow material to be left in (D) and (C), making such a joint possible.

H.- Lower member of lamp shade. The upper surf ce of this should be covered with thi k metal to act as a reflector.

I.- Vertical corner members of sh de. As before explained, these are secured to the cross supports (F) by mortise and tenon joints. The manner in which the upper ends of these pieces are to be mortised to receive the frame work (E) and drilled for the key, assuming this in position, will be readily understood from the drawing.

J-K- Upper, lower, and end rails for art glass sha e panels, showing how half lap joints are made and method of constructing corner joints.

L.- Frame for art glass top. The manner in which the two pieces, crossing at right angles are fra ed together at their point of intersection should be carefully studied as it is necessary that



A MECHANICAL COURSE FOR HIGH SCHOOLS.
By Robert A. Perkins.

PLATE	· Wood Working ·	DRAWN
· C ·	Course 52	BY R.A.P.

A Mechanical Course For High Schools.

this be a rigid joint. The number of fixtures and bending the lower ends will also be observed. It is necessary, for replacing lamps etc., that the whole top should be removed and for this reason, corner joints secured by slip pins were decided upon.

H.- Art glass.

I.- Metal strips of various forms holding glass in position and forming a neat finish where it meets the wood frame work.

Plate C, Course 32.

In many respects the most difficult of all the exercises, herein offered, is the combination chair and table designed in Prob. XI,D1, and here shown in isometric detail. Not only must all the joints be fitted accurately, but the sliding parts must move freely and without interference as well as without lost motion. The parts shown in detail are as follows:

A.- Chair legs, showing chamfered corners, tapered lower ends, and haunch tenon with chamfered edges at upper ends. The length of these tenons must be sufficient to al-

A Mechanical Course For High Schools.

low of th pin projecting above the upper cushion of the arms to admit a suitable cut for the top rail to provide clearance for the bracket (H).

B.- Arms of chair.

C.- Frame for seat, showing chamfered edges and tenons at mortise and tenon joints with legs.

D.- Molded bottom to support cushion seat of chair.

E.- Inner cross brace. This shows the general form of the brace to be cut to receive metal lug of bracket, as it moves from its central to its end position. It also indicates the manner in which the piece is fitted to the legs (L). This joint will be glued and countersunk with round headed screws.

F.- Bottom member of arm pocket.

G.- Front member of arm pocket, showing sheet metal receptacles, and form of hinges and chain. These will be held shut by a small catch fastened to (G) and slipping into a small slot in the lower face of (B).

H.- Metal brackets. The student should make the pattern for these pieces of tin which they should be cast of brass or made of malleable iron, finished and plated. These will be fastened to the top by round headed screws.

A Mechanical Course For High School.

I.- Top construction. This is identical to that employed in several of the preceding exercises. The top will consist of which this is constructed should be selected for color, grain, etc.; carefully glued and fitted; and finally, planed, scraped and sanded to a smooth and even surface. The side pieces of the top are not beveled, but they are to be glued in position as fully set in the small sketch of Plate X, D1.

The upholstering of the chair will, necessarily, be done under the personal direction of the instructor.

Plate D, Course S2.

The work bench, indicated in optional problem IV, D1, is plainly detailed in this plate. An explanation of the letters of reference follows:

A.- Bench top. This should be constructed of 1 3/4" birch or maple, glued up of several sections with end pieces rabbeted, glued and screwed to ends as shown.


R.
S.
D.
C.
A.
B.
J.
E.
D.
C.
A.
K.
N.
F.
A.
F.
O.
H.
G.
M.
I.
P.
N.
L.
G.
P.
Q.
P.
A.
B.
A.
K.
J.
K.
N.
O.
A MECHANICAL COURSE FOR HIGH SCHOOLS.
By Robert A Perkins.
PLATE D
WOOD WORKING
COURSE S2
DRAWN BY R.A.P.

A Mechanical Course For High Schools.

D.- Bottom of tool trough.

C.- Side of tool trough.

D.- Back of bench

E.- Chisel and small tool rack. This is reinforced by a metal strip around its outer edge which is fastened to D and to its end by small counter-sunk screws. It is further secured in position by small triangular braces.

F.- Apron of bench. This is joined into legs and secured to same by screws and glue.

G-J- End legs.

H.- Center legs.

(Note:- All the parts of bench, thus far mentioned, are to be secured in position by screws and glue. The screws are to be counter-sunk and are to have their heads covered by dowels (wirch if end finished flush with the various members.)

I.- Vise. The construction is plainly indicated. The screw with handle may either be made in the forge and machine shops or may be purchased at any hardware store.

J.- Rear legs. These are joined out to receive the parts (E) and (D).

A Mechanical Course for High Schools.

K.- Side supports of top pieces (L) and (L) and cross bracket of bench. These pieces are mitred to (F) at the corners; are cut out for the through dovetails of the parts (A),(B),(C), and (D) and are screwed to the legs and the various other members as explained in the text, given above.

L.- Lower jaw of vise. The steel pins and holes in the remarks adjacent are for various thicknesses of material being clamped in the vise.

M.- Steel pins which are inserted in the holes, shown in the top legs (K) and (L) and which are bent double, one end of which is bolted in the vise.

N.- Top and bottom guide of the planes, screwed to legs by brackets and through dowels and screwed to the block for planes guide.

O.- Bracket called a planes.

P.- Frame work of planes guides, also fig. 1 the two bar in detail. The pieces are dovetailed at their ends and fitted into the legs.

Q.- Base board mentioned from legs and screwed to lower front member (F) by screws and glue.

R.- Front corner joint of bench drawers.

A Mechanical Course for High School.

B.- Each course joint of two lumbers.

A rapid acting vise, Delaware tool, attached to one end of the bench is very convenient for small work and should be added where the student feels that he can afford to do so.

Plate 2, Course S2.

The hall block, designed in spherical problem V, Course D1, is shown in isometric sectional elevation in Plate 2; Figure 1, showing the construction of the cabinet; Figure 2, the base and; Figure 3, the detail of certain joints which will be enumerated in the following text. An explanation of the letters of reference follows:

A.- Top piece. These slope to the front and five and one, thirdeths, inward on ends that must be determined for each design with the assistance of the fundamentals.

B.- Ogee moulding, corresponding joints of (A) and (C), mitred at an angle of forty-five between the corners.



FIG. 1.



FIG. 2.



FIG. 3.

A MECHANICAL COURSE FOR HIGH SCHOOLS.
By Robert A. Perkins.

PLATE.		DRAWN BY
E.	WOOD WORKING COURSE S2	R.A.P.

A Mechanic's Cr[illegible] Box [illegible] Lock.

C.- U[illegible] members of [illegible] lock bolt [illegible]. These are secured to (D) by [illegible] similar to that shown in Fig. 2.

D.- Vertical [illegible] of [illegible] bolt. These are [illegible] to (C) [illegible] (E) by [illegible] as shown in Fig. 3.

E.- Bow [illegible] of [illegible] bolt.

F.- Section of [illegible] bolt.

G.- Raised [illegible] [illegible] [illegible] [illegible] [illegible] [illegible] [illegible] bolt as in Fig. 2.

L.- Upper middle [illegible] [illegible] [illegible] [illegible] [illegible] [illegible] [illegible]

[illegible]

.- [illegible]

c.- [illegible]

D.- [illegible]

.- [illegible]

.- Bottom [illegible]

[illegible]

[illegible]

27167
q607 P42
Perkins, D. A.
Mechanical course for U.S.

q607 27167 P42

Armour Institute of Technology
Library
CHICAGO, ILL.